CITY OF HIGH POINT AGENDA ITEM



Title: Construction Manager At Risk (CMAR) Professional Services Garney Companies, Inc. DBA Garney Construction Catalyst Project – Appling Way Change Order 4

From: Terry Houk – Public Services Director Derrick Boone – Public Services Asst. Director Meeting Date: August 19, 2019 Robby Stone – Public Services Asst. Director

Public Hearing:	N/A	Advertising Date:	N/A
		Advertised By:	N/A

Attachments: Attachment A – Change Order Documents Attachment B- Sketch- Appling Way

PURPOSE:

To approve Change Order No. 4 to the Garney Company, Inc. contract for the construction of Appling Way.

BACKGROUND:

On February 5, 2018, City Council awarded a contract to Garney Company, Inc. as the Construction Manager at Risk (CMAR) to provide support to the Public Services Department in upgrading and/or replacing infrastructure that would be impacted by the Catalyst Project.

The Public Services Department is now requesting approval of Change Order 4 to construct Appling Way. The project will include the construction of a new public road that will connect N. Elm Street and Pine Street. The roadway project will include the construction of sidewalk, streetscaping, curb and gutter, water/sewer utility lines, and storm drainage system.

BUDGET IMPACT:

Funds for this change order are available in the 2019-2020 budget.

RECOMMENDATION / ACTION REQUESTED:

Public Services is recommending that Council approve Change Order 4 to Garney Companies, Inc. in the amount of \$2,584,160.20.

APPLING WAY HIGH POINT, NORTH CAROLINA **CONSTRUCTION DOCUMENTS**

PROJECT #: 18-330

CLIENT: **CITY OF HIGH POINT** 211 S HAMILTON STREET HIGH POINT, NC 27260 (336) 883-8515

CIVIL ENGINEER:





P: 336.723.1067 F: 336.723.1069

DRAWING INDEX:

C-0.00	Cover
C-0.01	Project Notes
C-0.02	Project Notes
C-0.03	Legend Sheet
C-1.00	Demolition Plan
C-2.00	Overall Site Plan
C-2.01	Hardscape Enlargement Plans
C-3.00	Erosion Control Plan - Stage 1
C-3.01	Erosion Control Plan - Stage 2
C-3.20	Grading & Drainage Plan
C-4.00	Overall Utility Plan
C-4.01	Appling Way Plan & Profile
C-4.02	Sanitary and Storm Sewer Profiles
C-6.00	Erosion Control Details
C-6.01	Erosion Control Details
C-6.02	Erosion Control Details
C-6.03	Erosion Control Details
C-6.10	Storm Drainage Details
C-6.11	Storm Drainage Details
C-6.20	Utility Details
C-6.30	Site Details
C-6.31	Site Details
C-6.32	Site Details
C-6.33	Site Details
C-6.40	Typical Sections
L-1.00	Overall Landscape Plan
L-2.00	Landscape Notes, Specs & Details









NCBEES CERT. NO.: C-1347

PRELIMINARY DRAWING NOT FOR CONSTRUCTION

PROJECT:



CLIENT: CITY OF HIGH POINT

 \mathbf{O}

211 S HAMILTON STREET HIGH POINT, NC 27260 (336) 883-8515

DRAWN:	BWC
DATE:	5/20/19
REVISIONS:	
JOB. NO:	18-330
SHEET TITLE:	
COVER	



IN MUST

BEFORE YOU DIG! CALL 811 N.C. ONE-CALL CENTER IT'S THE LAW!

SURVEY DISCLAIMER:

THE BOUNDARY AND TOPOGRAPHIC INFORMATION HEREIN IS FROM SURVEY INFORMATION SUPPLIED BY: DAVIS, MARTIN, POWELL 6415 OLD PLANK ROAD HIGH POINT, NC 27265 (336) 886-4821 ELEVATION DATUM IS NAVD88

(Q) OWNER'S/DEVELOPER'S CERTIFICATE OF COMPLIANCE: I, _____, ACCEPT THIS SUBMISSION AS MY PLAN OF DEVELOPMENT AND AGREE TO INSTALL ALL REQUIRED IMPROVEMENTS AND COMPLY WITH THE CONDITIONS OF APPROVAL OWNER/DEVELOPER (J) <u>TECHNICAL REVIEW COMMITTEE ENDORSEMENT BLOCK FOR SITE PLANS:</u> APPROVED BY THE TECHNICAL REVIEW COMMITTEE FOR 18 MONTHS (DEV. # SP-17-0093) SUBJECT TO THE APPROVAL OF ANY REQUIRED STREET AND UTILITY PLANS AND PROFILES AND APPROVAL OF A SEPARATE

Date

LAND-DISTURBING PERMIT AND/OR EROSION CONTROL PLAN. Director of Planning and Development

SCALE: 1" = 60'





August 8, 2019

Mr. Terry Houk Public Services Director **City of High Point** 211 S. Hamilton Street High Point, NC 27261

Re: Change Order No. 4 City of High Point Mixed Use Development - CMAR City of High Point, North Carolina CHP Contract 29-012418 Hazen No.: 32140-010

Dear Mr. Houk,

Please find a digital copy of Change Order No. 4 for the City of High Point Downtown Mixed Use Project - Utility Improvements enclosed. This change order is to cover the additional Guaranteed Maximum Price to complete the construction of the road, waterline, sanitary sewer line, and storm drain for the new Appling Way.

The total amount for Change Order #4 is \$2,584,160.20. A breakdown of the changes is presented in the table on the next page.

Contract Task No.	Amount	Calendar Days
Original Contract Value	\$89,131.00	-
Change Order # 1 (Approved August 28, 2018)	\$3,265,862.13	170
Change Order # 2 (Approved May 14, 2019)	\$3,867,682.18	342
Change Order #3 (Approved August 5, 2019)	\$723,972.91	0
Change Order #4		
Appling Way GMP	\$2,584,160.20	0
Subtotal for Change Order #4	\$2,584,160.20	0
Revised Total Contract Amount	\$10,530,808.42	513



The backup to the Contractor's GMP is attached. Please contact me at (336) 478-3372 if you shall have any questions or require additional information.

Regards,

Christy Nelson

Christy Nelson, PE Principal Engineer

Enclosures

Cc: Terry Houk, City of High Point, North Carolina Aaron Babson, P.E., Hazen and Sawyer



Change Order No. 4

Date of Issua	nce: August 8, 2019	Effective Date:						
Owner:	City of High Point, NC	Owner's Contract No.:	29-012418					
Contractor:	Garney Companies, Inc., DBA Garney Construction	Contractor's Project No.:	2264					
Engineer:	Hazen and Sawyer	Engineer's Project No.:	32140-010					
Project:	Downtown Mixed Use Project - Utilities Improvements	Contract Name:	Appling GMP					

The Contract is modified as follows upon execution of this Change Order:

Description: Contractor will provide the services outlined in the attached documents to construct the water, sewer, and storm improvements inside the designated project area per the contract documents for Lindsay Place and English Rd. This change order also captures the additional costs and days required to address additional cost items for Elm St Construction and CMAR management and admin fees to install approximately 650 ft of sanitary sewer on Lindsay St.

 Attachments:
 Appendix A: Change Order Support Documentation and Terms;

 Appendix B: Garney Construction Guaranteed Maximum Price;

 Appendix C: Contract Documents;

 Appendix D: Payment and Performance Bonds

CHANGE IN CONTRACT PRICE	CHANGE IN CONTRACT TIMES						
Original Contract Price:	Original Contract Times: Substantial Completion: NA						
\$ 89,131.00	Ready for Final Payment: NA						
	days or dates						
Increase from previously approved Change Order No. <u>1-3</u> :	Increase from previously approved Change Order No. <u>1-3</u> :						
	Substantial Completion: January 10, 2020						
\$ <u>7,857,517.22</u>	Ready for Final Payment: <u>January 23, 2020</u>						
Contract Price prior to this Change Order:	Contract Times prior to this Change Order:						
	Substantial Completion: <u>January 10, 2020</u>						
Ş <u>7,946,648.22</u>	Ready for Final Payment: <u>January 23, 2020</u>						
Increase of this Change Order:	Increase of this Change Order:						
\$ 2,584,160,20	Substantial Completion: <u>343 days</u>						
52,584,100.20	days or dates						
Contract Price incorporating this Change Order:	Contract Times with all approved Change Orders:						
contract the incorporating this change order.	Substantial Completion: January 23, 2020						
\$10,530,808.42	Ready for Final Payment: January 23, 2020						
RECOMMENDED: ACCE	PTED: ACCEPTED:						
By: <u>Christy Nelson</u> By:	Ву:						
Engineer (if required) Owner (Aut	horized Signature) Contractor (Authorized Signature)						
Title: Principal Engineer Title	Title						
Date:	Date						
Approved by Funding Agency (if applicable)							
Ву:	Date:						
Title:							
EJCDC [®] C-941, Char	nge Order.						
Prepared and published 2013 by the Engineers Page 1 of	Joint Contract Documents Committee. 1						

APPENDIX A CHANGE ORDER NO. 4 SUPPORT DOCUMENTATION AND TERMS

DOWNTOWN MIXED USE PROJECT CONSTRUCTION MANAGER AT RISK AGREEMENT

APPLING WAY CONSTRUCTION PHASE SERVICES

City of High Point Contract Number <u>29-012418</u>

PROJECT: Change Order No. 4 is for the construction phase services for the utility improvements along the new Appling Way in the project area and is the fourth phase of the previously designated Project generally described as "Downtown Mixed Use Project" ("the Project").

CHANGE ORDER DOCUMENTS:

- a. Determination of Change Order Costs and Backup Documentation
- b. Determination of Change Order Schedule
- c. Determination of Contingencies
- d. Appendix B: CMAR (Garney Construction) Appling Way GMP
- e. Appendix C: Project Drawings and Specifications for Appling Way as incorporated with Change Order No. 4.
- f. Appendix D: Payment Bond and Performance Bond.

CMAR'S WORK ON THE PROJECT: The CMAR's work shall consist of Construction Phase Services ("the CMAR's Work") as described in the Original Agreement and amended herein.

CONSTRUCTION PHASE SERVICES: The requirements of the CMAR during Construction Phase Services are outlined in the Agreement and supplemented with the information included in this document.

CMAR'S GUARANTEED MAXIMUM PRICE: The CMAR will provide the services included in the Agreement and this Change Order as summarized below and detailed in the proposal from the CMAR found in Appendix B.

Appling Way Guaranteed Maximum Price	\$2,584,160.20
CMAR Contingency:	\$380,000.00
Subcontractor Markup:	\$167,356.00
Subcontractor Cost:	\$1,673,560.00
General Conditions (G&A):	\$60,830.99
CMAR Labor /Management Fees:	\$302,413.21
Appling Way GMP	

Change Order No. 4 Total

\$2,584,160.20

CONTINGENCIES: Contingencies shall be as described in the Agreement.

- a. CMAR CONTINGENCY SHARE: If contingency funds are remaining in the CMAR Contingency at the completion of the project, the remaining funds shall be shared between the Owner and CMAR at a 75% 25% split, respectively.
 - i. Total CMAR Contingency Summary To Date

1. Change Order No. 1 – N. Elm St.	\$200,000
2. Change Order No. 2 – Lindsay and English	\$350,000
3. Change Order No. 3 – Pine St.	\$100,000
4. Change Order No, 4 – Appling Way	\$380,000

CONTRACT DOCUMENTS: The Documents include the contract drawings for the addition of Appling Way in Appendix C. The project manual with technical specifications from Change Order No. 1 will be incorporated by reference.

CMAR'S PERFORMANCE: The CMAR will perform the CMAR's Work in a timely fashion in accordance with the requirements of the Contract Documents. The CMAR's Work includes the proper and timely completion of its responsibilities with respect to the construction of the Project through the employment of best construction management practices.

CMAR'S SCHEDULE: The CMAR will deliver a project at a final completion time no later than January 23, 2020. Time extensions include 0 calendar days for Appling Way construction.

CMAR'S CONSTRUCTION PHASE SERVICES COMPENSATION. Payments for the Construction Phase services shall be proposed as follows.

- a. The CMAR may submit a partial payment application at a frequency no more than once per calendar month during the project and according to the procedures included in the Original Agreement.
- b. Labor/Management Fees shall be monthly at a frequency of six (6) equal installments in the first six (6) months of the project. If the Contractor finishes prior to the sixth partial payment, the Contractor may invoice for the remainder of the L/M Fees.
- c. General and Administrative Fees shall be monthly at equal installments. If the

Contractor finishes prior to the final partial payment, the Contractor may invoice for the remainder of the G&A Fees.

- d. Subcontractor Costs shall be included monthly in the partial payment request and submitted in the Schedule of Values acceptable to the C/A and Owner, and paid in accordance with actual completed work.
- e. Subcontractor Markup shall be charged in accordance with Item "d" at the negotiated markup rate of 10%.
- f. Contingencies: Contingencies will be accessed by completed Work Change Directives indicating which project contingency is accessed and shall be paid in accordance with the actual work completed.

PAYMENT BOND AND PERFORMANCE BOND: Upon acceptance by the City of the CMAR's GMP for the Construction Phase Services, the CMAR will provide a payment bond and a performance bond, each in the amount of the GMP, for the CMAR's Construction Phase Services in the form set forth in this Agreement. These payment bonds and performance bonds are required to ensure the CMAR's full and proper performance of the CMAR's Work and the CMAR's full and prompt payment of all subcontractors and suppliers providing labor or materials relating to the Project. The surety on the payment bonds and performance bonds, by providing these bonds, agrees to be bound by the terms of the Agreement, and agrees to perform any action and make any payment required under the Agreement that the CMAR fails to perform or make.

City of High Point Project Number <u>29-012418</u> ("the Project")

Change Order No. 4

APPENDIX B

• Garney Construction Guaranteed Maximum Price Proposal for Appling Way



City of High Point

Downtown Mixed-Use Project

CMAR Construction Services

		Project	Managem	nent				Cost Estin	nator(s) Superintendent		endents	Other		
6/21/2018	PIC	Pcon Mgr	Sr. PM	РМ	Asst PM	Proj Eng	Chief Est.	Safety Prof.	Estimator	Assistant Super	Super	Admin	Total Hours	Total Labor Costs
Hourly rate	\$204.00	\$124.67	\$161.70	\$129.80	\$107.80	\$90.20	\$136.40	\$107.80	\$79.20	\$121.00	\$135.30	\$52.80		00010
Scope of Services														
A. Labor Costs														
Lindsay Street								,,						
bid phase	2		12	30		40	15				15	10	124	\$ 14,453.89
Const month 1 (January covered in English)			16	24		40							88	\$ 10,942.36
Feb	8		16	40		100					200	10	374	\$ 46,019.16
March	8		16	40		100					200	10	374	\$ 46,019.16
April	8		16	40		100					200	10	374	\$ 46,019.16
Мау	8		16	40		100					200	10	374	\$ 46,019.16
June	8		16	40		100					200	10	374	\$ 46,019.16
July	8		16	40		110					200	10	384	\$ 46,921.16
													-	\$ -
													-	\$ _
Subtotal - Hours / Position	58	-	124	294	-	690	15	-	-	-	1,215	70	2,466	\$ 302,413.21

Section A. Total	57	-	118	279	-	670	8	-	-	-	1,208	65		2,404	\$	302,413.21
------------------	----	---	-----	-----	---	-----	---	---	---	---	-------	----	--	-------	----	------------



City of High Point

Downtown Mixed-Use Project

CMAR Construction Services

		Project	Manageme	ent			Cost Estimator(s)		Superint	endents	Other			
6/21/2018	PIC	Pcon Mgr	Sr. PM	РМ	Asst PM	Proj Eng	Chief Est.	Safety Prof.	Estimator	Assistant Super	Super	Admin	Total Hours	Total Labor Costs
	Total													
B. General Conditions	Cost													
G&A - 5% Total Labor Costs	\$15,120.66	Ď.												
Bonds (2%) & Insurance (0.5%) = 2.5%	\$7,560.33	3												
Vehicles	\$ 13,800.00													
Fuel	\$ 8,400.00	_												
Management travel - \$1000/month	\$ 5,000.00													
Regional Safety / Safety Equipment / Train	\$ 3,500.00													
Office / Document Expense	\$ 7,200.00													
Ovenight Mail Expense	\$ 250.00													
Section B. Total	\$ 60,830.99													
Total A + B	\$ 363,244.20													
C. Subcontract Expense														
Appling cost	\$ 1,673,560.00													
Section C. Total	\$ 1,673,560.00													
Total A + B + C	\$2,036,804.20	<u>)</u>												
Fee = 10% on Subcontract Expense	\$167,356.00	D												
Revised Total	\$2,204,160.20	D												
Project Contingency	\$380.000.00	'n												
Owner's Contingency	¢000,000.00	, n												
owner a contingency		21												
		7												
Project GMP	\$2,584,160.20)												

SIZE	DESCRIPTION	Contract		UNIT PRICE	Total Amount
		Amount			
	WATER LINE				
	8" Restrained DIP Water line	595.00	LF	\$ 100.00	59,500.00
	8" Gate Valve with box	2.00	EA	\$ 3.500.00	7.000.00
	8" Fitting w/ Accessories	13.00	EA	\$ 1,500.00	19,500.00
	6" DIP	50.00	LF	\$ 80.00	4,000.00
	6" Gate valve with box	3.00	EA	\$ 3,000.00	9,000.00
	6" Cap w/Accessories	3.00	EA	\$ 1,000.00	3,000.00
	4" DIP	16.00	LF	\$ 80.00	1,280.00
	4" Gate Valve with Box	1.00	EA	\$ 2,500.00	2,500.00
	4" Cap w/ Accessories	1.00	EA	\$ 1,000.00	1,000.00
					0.00
	1.5" Irrigation service (include tap, copper pipe, curb stop, coorperation and other associated items)	1.00	EA	\$ 3,500.00	3,500.00
	FH (tee, valve, and other bid items)	1.00	EA	\$ 7,000.00	7,000.00
	Reinstall Existing FH (tee, valve, and other bid items)	1.00	EA	\$ 6,000.00	6,000.00
	Removal of 6 inch Meter Vault "Stickleys"	1.00	LS	\$ 2500.00	2,500.00
	Adjust Existing Water Meter to Finished Grade	1.00	EA	\$ 1,000.00	1,000.00
	SEWER				
	8" DIP Sanitary Sewer	308.00	LF	\$ 95.00	29,260.00
	4' dia manhole	4.00	EA	\$ 3,800.00	15,200.00
	Core Ex. Manhole	1.00	EA	\$ 2,000.00	2,000.00
	Rotate existing MH cone & lid outside of propoesed curv and adjust rim to finished grade	1.00	ΕA	\$ 3,300.00	3,300.00
	Tie in Existing Service to Stickley	1 00	FΔ	\$ 2 000 00	2 000 00
		1.00	2/1	\$ 2,000.00	2,000.00
	STORM DRAIN			1	1
	Convert existing Double Inlet to SDMH	1.00	EA	\$ 5,500.00	5,500.00
	30" RCP Pipe	27.00	LF	\$ 80.00	2,160.00
	24" RCP Pipe	257.00	LF	\$ 75.00	19,275.00

 15" RCP Pipe	375.00	LF	\$ 65.00	24,375.00
5' Diameter MH	1.00	EA	\$ 5,000.00	5,000.00
Double Catch Basin	1.00	EA	\$ 9,000.00	9,000.00
Standard Catch Basin	11.00	EA	\$ 4,000.00	44,000.00
NCDOT Drop Inlet	1.00	EA	\$ 4,000.00	4,000.00
DEMO / MISC				
Grading and 12" of suitable fill under roadway	1.00	LS	\$ 55 <i>,</i> 000.00	55,000.00
Retaining Wall Removal	1.00	LS	\$ 25,000.00	25,000.00
Construction Entrance	2.00	EA	\$ 3,500.00	7,000.00
Concrete/Asphalt Removals	1.00	LS	\$ 20,000.00	20,000.00
Misc Removal (includes items not covered curb, sidewalk, asphalt removals)	1.00	LS	\$ 15,000.00	15,000.00
Bollard Removal	1.00	LS	\$ 1,200.00	1,200.00
Bollard Installation	5.00	EA	\$ 1,000.00	5,000.00
Erosion Control	1.00	LS	\$ 25,000.00	25,000.00
Restoration including matting and seeding	1500.00	SY	\$ 4.00	6,000.00
Temp Seeding	2.00	Acre	\$ 500.00	1,000.00
Driveway Apron (Includes proper depth of concrete 4500psi and 6" ABC Base)	4.00	Ea	\$ 3500.00	14,000.00
Curb & Gutter Install	1000.00	LF	\$ 58.00	58,000.00
Valley Curb & Gutter Install	575.00	LF	\$ 52.00	29,900.00
Concrete Side Walk Install (concrete for Driveway apron not inculded in this bid item) 4" 3000 PSI concrete	1290.00	SY	\$ 65.00	83,850.00
Concrete Side Walk Install (concrete for Driveway apron not inculded in this bid item) 5" 4500 PSI concrete with 6" ABC base	590.00	SY	\$ 67.00	39,530.00
Concrete Side Walk Install (concrete for Driveway apron not inculded in this bid item) 6" 4500 PSI concrete with 6" ABC base	395.00	SY	\$ 72.00	28,440.00
Stamped Asphalt	250.00	SY	\$ 140.00	35,000.00
Brick Paving (vehicular traffic rated) includes 4" thick concrete base, 1" sand bedding (or mortar for single and double row border) and weep holes through concrete 24" OC	200.00	SY	\$ 1,450.00	290,000.00
			A 40 000 00	10.000.00
 Pavement Striping (Thermo Striping)	1.00	LS	\$ 12,000.00	12,000.00
 Asphalt Base Pavement	620.00	ΓN TN	\$ 153.00	94,860.00
 Asphait Intermediate Pavement	420.00	TN	\$ 160.00	67,200.00
 Asphalt Surface Pavement	320.00	ſΝ	\$ 170.00	54,400.00
Mill and overlay	200.00	SY	\$ 90.00	18,000.00
Concrete Paved Ditch	80.00	LF	\$ 125.00	10,000.00

Traffic Control	1.00	LS	\$ 6,000.00	6,000.00
GIS Survey of Final Project	1.00	LS	\$ 10,000.00	10,000.00
ADA Trench Drain	20.00	LF	\$ 500.00	10,000.00
15" Nyloplast drain basin	1.00	Ea	\$ 1500.00	1,500.00
15" Inch HDPE	20.00	LF	\$ 100.00	2,000.00
Unsuitable Material (pipe trench)	1439.00	CY	\$ 70.00	100,730.00
Concrete Swale	1.00	Ea	\$ 8,000.00	8,000.00
ADA Ramp	2.00	EA	\$ 2,500.00	5,000.00
10" Sch 40 Roof Leader (includes tie into storm drain, and fittings)	15.00	LF	\$ 90.00	1,350.00
10" Nyloplast Drain Basin for Roof Leader	1.00	Ea	\$ 1500.00	1,500.00
Tree pit Drainage	125.00	LF	\$ 90.00	11,250.00
Construction Staking	1.00	LS	\$ 27,000.00	27,000.00
Planting (includes go to detail)	1.00	LS	\$ 140,000.00	140,000.00
Mobilization	1.00	LS	\$ 62,000.00	62,000.00
			Total Contract	
			Amount	1,673,560.00

Assumption log

STRUCTURE	STRU #	DIV #	Bid Assumptions	Answer
			1.5 Irrigation service line will be copper	
General Conditions	GC		cut and fill calcultated off of needing 12 inches of fill below asphalt totaling 2 ft	
			from bottom of fill dirt to top of proposed asphalt.	
			contractor to have 8 months time to complete once utilities relocated	
			roof drain and tree pit drain priced per measurments from drawings	
			Garny has not included any management fees for weather days over the average.	
			assuming rain days from table attached. A rain day includes any day more than	
			.1" of rain or any day that site conditions are determined too muddy for the work	
			going on by site inspector.	
			meter vaults and meters installed by others. Install pipe and cap	
			permits already obtained	
			an easements obtained retaining wall and design excluded	
			no coordination work with utility owners included	
			all conflicting utilities including overhead power moved before contractor on site.	
			no overlay of existing parking lot.	
			Pedestiran and stadium traffic excluded	
			Traffic plans if required by others	
			Exclude adjusting monitoring well to finished grade	
			Working through ball games	
			Gas and Communication is by others and not included in this pricing	
			Striping of existing parking lot is not included in this pricing	
			Striping is based on Thermo for the Center line only. No other striping included	
			light poles and removing existing light poles are not included in this pricing	
			duct bank will be installed prior to any concrete curb/sidewalk/etc or we have	
			the drawing of where to be installed so as not to delay our work	
			no warranty on vegitation included no watering of vegitation included	
			only anticipating crossing underground utilities shown on drawings in pricing	
			Excluding all coordination with any existing utilities.	
			existing vault at Elm st waterline assume removing top and filling back in after tie	
			In	
			excluding all site lighting and conduit for site lighting	
			all normits and assemants in hand hy start of construction (October 1, 2010)	
			naving priced by Detail 6 (Asphalt Paving) on Sheet C-6 40	
			excluding working around any other contractors or work in the area. No other contractors or construction to be within construction limits while we are working	
			assuming that the chain link fence that is currently allong the proposed Appling way stays in place	
			Plan start date of January 2020	
			Tree Pits with and without Grates included in the Planting	
			Engineering/Geotechnical Report for Road stabilization design by others	
			Value Engineering ideas	Rough estimated saving
			Make sewer PVC	\$ 7,000.00
			change brick work to stamped concrete	\$ 200,000.00
			delete valve at Elm (already have one in street)	\$ 4,000.00
			Dirt savings in tree wells if change spec to get from closer to High Point	\$ 2,000.00
			reduce paving thickness if undercut required	IBD based on now thick needed
	<u> </u>		changing waterline from restrained joint to push joint	\$ 10,000.00
	1			
	1			

City High Point Mixed Use Utility Project Englis Street

RISK REGISTER

ID #	DESCRIPTION OF RISK (INCLUDING ANY IDEN TIFIED TRIGGERS)	IMPACT ON PROJECT (IDENTIFY CONSEQUENCES)	ASSESSMENT OF LIKELIHOOD (1-5)	ASSESSMENT OF SERIOUSNESS (1-5)	SEVERITY (1-25)	MITIGATION ACTIONS (PREVENTATIVE OR CONTINGENCY)	Contingency Owner	Project	Owner	FINAL RESULT
1	Utilities not shown on drawings	Downtime with crew	5	5	25	pre job locates		\$ 25,000.00		
		conflict with new lines (relocate)	2	4	15	Soft Digs		\$ 2,500.00		
2	Geo tech info	ground water	4	2	15	Maybe at Pine		\$ 5,000.00		potholes show minor.
		plan changes	1	1	25			\$ 25,000.00		can we dump in sanitary if required
		bad material	3	1	2	unsuitable bid item for projecthow much is contaminated		\$ 55,000.00		adder for contaminated material
		undercut and add bedding	1	2	8	add stone cost and labor wet material		\$ 20,000.00		
		Rock	1	1	1	change spec in project desc. To unclassified Exc		\$-		no rock on report
		Geofabric and suitable fill	5	5	24	if geofabric needed - dig down place fabric, haul off, haul in good material		\$ 250,000.00		
4										
5								\$-		
21		TOTAL						\$ 382,500.00	\$-	

City of High Point Project Number <u>29-012418</u> ("the Project")

Change Order No. 4

APPENDIX C Contract Documents

APPLING WAY HIGH POINT, NORTH CAROLINA **CONSTRUCTION DOCUMENTS**

PROJECT #: 18-330

CLIENT: **CITY OF HIGH POINT** 211 S HAMILTON STREET HIGH POINT, NC 27260 (336) 883-8515

CIVIL ENGINEER:





P: 336.723.1067 F: 336.723.1069

DRAWING INDEX:

C-0.00 C-0.01 C-0.02 C-0.03 C-1.00 C-2.00 C-2.01 C-3.00 C-3.01 C-3.20	Cover Project Notes Project Notes Legend Sheet Demolition Plan Overall Site Plan Hardscape Enlargement Plans Erosion Control Plan - Stage 1 Erosion Control Plan - Stage 2 Grading & Drainage Plan
C-3.01	Erosion Control Plan - Stage 2
C-3.20	Grading & Drainage Plan
C-4.00	Overall Utility Plan
C-4.01	Appling Way Plan & Profile
C-4.02	Sanitary and Storm Sewer Profiles
C-6.00	Erosion Control Details
C-6.01	Erosion Control Details
C-6.02	Erosion Control Details
C-6.03	Erosion Control Details
C-6.10	Storm Drainage Details
C-6.11	Storm Drainage Details
C-6.20	Utility Details
C-6.30	Site Details
C-6.31	Site Details
C-6.32	Site Details
C-6.33	Site Details
C-6.40	Typical Sections
L-1.00	Overall Landscape Plan
L-2.00	Landscape Notes, Specs & Details









NCBEES CERT. NO.: C-1347

PRELIMINARY DRAWING NOT FOR CONSTRUCTION

PROJECT:



\mathbf{O} Ž

CLIENT:

CITY OF HIGH POINT 211 S HAMILTON STREET HIGH POINT, NC 27260 (336) 883-8515



SCALE: 1" = 60' SHEET NO .:

C-0.00



ION MUST

BEFORE YOU DIG! CALL 811 N.C. ONE-CALL CENTER IT'S THE LAW!

SURVEY DISCLAIMER:

THE BOUNDARY AND TOPOGRAPHIC INFORMATION HEREIN IS FROM SURVEY INFORMATION SUPPLIED BY: DAVIS, MARTIN, POWELL 6415 OLD PLANK ROAD HIGH POINT, NC 27265 (336) 886-4821 ELEVATION DATUM IS NAVD88

(Q) OWNER'S/DEVELOPER'S CERTIFICATE OF COMPLIANCE:	
I,, ACCEPT THIS SUBMISSION	AS MY PLAN OF DEVELOPMENT AND AGREE TO
INSTALL ALL REQUIRED IMPROVEMENTS AND COMPLY WIT	TH THE CONDITIONS OF APPROVAL
OWNER/DEVELOPER	Date
(J) TECHNICAL REVIEW COMMITTEE ENDORSEMENT BLOCK F	OR SITE PLANS:
APPROVED BY THE TECHNICAL REVIEW COMMITTEE FOR	18 MONTHS (DEV. # SP-17-0093) SUBJECT TO THE
APPROVAL OF ANY REQUIRED STREET AND UTILITY PLANS	S AND PROFILES AND APPROVAL OF A SEPARATE
LAND-DISTURBING PERMIT AND/OR EROSION CONTROL PL	AN.

Director of Planning and Development

Date

© STIMMEL ASSOCIATES, P.A.

GENERAL NOTES:

- 1. THE CONTRACTOR SHALL VISIT THE SITE TO INFORM AND SATISFY HIMSELF OF ALL EXISTING CONDITIONS PRIOR TO SUBMITTING HIS BID. ANY DISCREPANCY BETWEEN THE SITE AND THOSE CONDITIONS REPRESENTED ON THE DRAWINGS SHALL BE BROUGHT TO THE ATTENTION OF THE OWNER AND THE ENGINEER IMMEDIATELY.
- 2. ALL DIMENSIONS, RADII, AND NORTHING & EASTING COORDINATES ARE TO FACE OF CURB, CENTER OF STRUCTURES SUCH AS INLETS, MANHOLES, ETC., OR END OF PIPE RUNS AS APPLICABLE UNLESS NOTED OTHERWISE ON THE PLANS.
- 3. ALL EXISTING UTILITIES OR STRUCTURES INDICATED ON THE DRAWINGS ARE BASED ON AVAILABLE INFORMATION OF RECORD. THE CONTRACTOR IS REQUIRED TO TAKE PRECAUTIONARY MEASURES TO PROTECT EXISTING BUILDINGS/ STRUCTURES AND UTILITY LINES SHOWN HEREON AND ANY OTHER EXISTING LINES NOT OF RECORD OR NOT SHOWN ON THESE PLANS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAKING ARRANGEMENTS FOR THE PROTECTION, RELOCATION OR REMOVAL OF CONFLICTING EXISTING UTILITIES AND AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES RESULTING FROM HIS FAILURE TO LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES. BEFORE STARTING WORK THE CONTRACTOR SHALL CONTACT NC 811 TO HAVE ALL EXISTING UTILITIES LOCATED.
- 4. LOCATION AND ELEVATIONS OF IMPROVEMENTS, TO BE MET OR CROSSED BY WORK, SHALL BE CONFIRMED BY FIELD MEASUREMENT, SUFFICIENTLY AHEAD OF CONSTRUCTION TO PERMIT REVISIONS TO THE PLANS, IF REVISIONS ARE NECESSARY DUE TO ACTUAL LOCATION OF EXISTING UTILITIES.
- 5. THE CONTRACTOR SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY. THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS. THE CONTRACTOR SHALL DEFEND, INDEMNIFY, AND HOLD THE OWNER AND THE ENGINEER HARMLESS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED IN CONNECTION WITH PERFORMANCE OF WORK ON THIS PROJECT, EXCEPTING FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR THE ENGINEER.
- 6. THE CONTRACTOR SHALL VERIFY THAT ALL REQUIRED PERMITS AND APPROVALS HAVE BEEN OBTAINED FROM THE APPROPRIATE AUTHORITIES BEFORE BEGINNING WORK ON THE PROJECT.
- 7. ALL CONSTRUCTION, MATERIALS, AND WORKMANSHIP SHALL CONFORM TO THE FOLLOWING:
- EROSION CONTROL NCDEQ LAND QUALITY SECTION'S "EROSION AND SEDIMENTATION CONTROL PLANNING AND DESIGN MANUAL", CITY OF HIGH POINT EROSION CONTROL STANDARDS
- STORM DRAINAGE NCDOT STANDARDS AND SPECIFICATIONS; CITY OF HIGH POINT STANDARD DRAWINGS
- WATER AND SANITARY SEWER CITY OF HIGH POINT STANDARDS & SPECIFICATIONS
- ASPHALT PAVEMENT, CURB & GUTTER NCDOT STANDARDS AND SPECIFICATIONS IN THE EVENT OF A CONFLICT BETWEEN THE DRAWINGS AND THESE STANDARDS, THE MORE
- STRINGENT REQUIREMENT SHALL APPLY AS DETERMINED BY THE ENGINEER.
- 8. THE SITEWORK CONTRACTOR IS RESPONSIBLE FOR COORDINATING HIS WORK WITH THE WORK OF OTHER CONTRACTORS ON THE PROJECT TO AVOID CONFLICT.
- 9. CONTRACTOR IS RESPONSIBLE FOR ALL EXCAVATION WORK INCLUDING, BUT NOT LIMITED TO, THE DESIGN, INSTALLATION AND MAINTENANCE OF SHEETING, SHORING AND BRACING; PROTECTION OF SLOPES; UNDERPINNING; AND DEWATERING IN ACCORDANCE WITH ALL LOCAL, STATE, FEDERAL AND OSHA STANDARDS. THE CONTRACTOR SHALL ENGAGE THE SERVICES OF A QUALIFIED PROFESSIONAL ENGINEER REGISTERED IN THE STATE OF NORTH CAROLINA TO DESIGN THE TEMPORARY SHEETING, SHORING AND BRACING IF REQUIRED FOR THE EXECUTION OF THE PROPOSED WORK.

SITE NOTES:

- 1. ALL RETAINING WALLS REQUIRE BUILDING PERMITS.
- 2. PATCH / REPAIR CURB & GUTTER, ASPHALT PAVING, CONCRETE SIDEWALKS AND OTHER SURFACES IMMEDIATELY AFTER COMPLETION OF UTILITY INSTALLATIONS AND OTHER SITE WORK.

MAINTENANCE & PROTECTION OF TRAFFIC:

CONTRACTOR IS RESPONSIBLE FOR THE DESIGN AND MAINTENANCE OF TEMPORARY TRAFFIC MANAGEMENT ASSOCIATED WITH DEMOLITION AND CONSTRUCTION. DESIGN SHALL BE BASED ON THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (MUTCD) - PART 6 TEMPORARY TRAFFIC CONTROLS AND IN ACCORDANCE WITH NCDOT REQUIREMENTS. CONTRACTOR IS RESPONSIBLE FOR ALL MAINTENANCE AND PROTECTION OF TRAFFIC CONTROL DEVICES.

SPECIFICATIONS:

1. THERE ARE ADDITIONAL NOTES, SPECIFICATIONS AND REQUIREMENTS CONTAINED. THROUGHOUT THE PLAN SET AS WELL AS REFERENCES TO SPECIFICATIONS FROM APPLICABLE GOVERNING AUTHORITIES AND INDUSTRY STANDARDS.

CONSTRUCTION STAKING & AS-BUILT NOTES:

- 1. CONSTRUCTION STAKING SHALL BE THE CONTRACTOR'S RESPONSIBILITY. STAKING SHALL BE PERFORMED BY A PROFESSIONAL LAND SURVEYOR. CONTRACTORS WITH GPS EQUIPMENT AND THE CAPABILITY TO SELF-PERFORM CONSTRUCTION STAKING MAY DO SO, HOWEVER CONTRACTOR SHALL ENGAGE THE SERVICES OF A PROFESSIONAL LAND SURVEYOR TO ESTABLISH HORIZONTAL AND VERTICAL CONTROL POINTS FOR THE PROJECT. THESE CONTROL POINTS SHALL BE USED TO CONFIRM THE ACCURACY OF THE GPS EQUIPMENT. CHECKS SHALL BE PERFORMED ON THE EQUIPMENT PERIODICALLY THROUGHOUT THE CONSTRUCTION PROCESS.
- 2. CONTRACTOR SHALL PROVIDE AS-BUILT SURVEY OF THE WATER, SANITARY SEWER, AND STORMWATER CONVEYANCE SYSTEM TO THE ENGINEER UPON COMPLETION OF CONSTRUCTION OF THOSE SYSTEMS. AS-BUILT SURVEY SIGNED & SEALED BY A PROFESSIONAL LAND SURVEYOR SHALL BE SUBMITTED TO THE ENGINEER IN PDF & CAD FORMAT WITHIN 30 DAYS OF COMPLETION OF UTILITY WORK. AS-BUILT SURVEY MAY BE REQUIRED SOONER TO ALLOW ADDITIONAL TIME FOR RECORD DRAWING PREPARATION BY ENGINEERING & APPROVAL BY REGULATING AGENCY AND PENDING TIME FRAMES FOR CO/TCO (CONTRACTOR TO PLAN ACCORDINGLY).
- 3. CONTRACTOR SHALL PROVIDE AS-BUILT SURVEY ELEVATIONS OF WATER LINES AT CROSSINGS WITH SANITARY SEWER AND STORMWATER PIPE TO THE ENGINEER DOCUMENTING THAT ALLOWABLE SEPARATION IS PROVIDED. SEE UTILITY NOTES FOR MINIMUM VERTICAL SEPARATION REQUIREMENTS.

STORM DRAINAGE NOTES:

- ALL STORM DRAINAGE CONSTRUCTION SHALL CONFORM TO NCDOT STANDARDS AND SPECIFICATIONS.
- 2. ALL STORM DRAINAGE STRUCTURES SHALL BE DESIGNED IN ACCORDANCE WITH NCDOT 840.46 (TRAFFIC BEARING PRECAST). STRUCTURES SHALL HAVE SOLID WALLS. WAFFLE WALL STRUCTURES WILL NOT BE ACCEPTED. STRUCTURES 10 FEET OR MORE IN DEPTH SHALL BE 4'x4' MINIMUM INSIDE DIMENSIONS REGARDLESS OF PIPE SIZE. ALL PIPE OPENINGS SHALL BE CAST OR CORED.
- CURB INLET STRUCTURES (DENOTED AS CI # ON PLANS) SHALL CONFORM DIMENSIONALLY TO NCDOT STANDARD 840.02. FRAMES AND GRATES SHALL BE U.S. FOUNDRY - MODEL 5181. TYPE "E, F, AND G" GRATES SHALL BE PROVIDED AS APPLICABLE.
- 4 GRATE INLET STRUCTURES (DENOTED AS DI # ON PLANS) SHALL CONFORM TO NCDOT STANDARDS 840.14 OR 840.15 WITH NCDOT STANDARD 840.16 FRAME AND GRATE.
- STORM DRAINAGE MANHOLES SHALL BE PRECAST CONCRETE CONFORMING TO NCDOT STANDARD 840.52. MANHOLES SHALL ALSO BE CONSTRUCTED IN ACCORDANCE WITH ASTM C-478, ASTM A-615, ASTM A-185 AND ASTM C-990. MANHOLE CASTINGS SHALL BE PROVIDED IN ACCORDANCE WITH THE SPECIFICATIONS.
- THE INVERTS OF ALL STORM DRAINAGE STRUCTURES SHALL BE GROUTED TO COMPLETELY 6 DRAIN AND NOT HOLD WATER.
- DUAL WALL HIGH DENSITY POLYETHYLENE PIPE (HDPE) WITH SOIL TIGHT JOINTS (ST) SHALL 7. CONFORM WITH THE FOLLOWING:
- PIPE SPECIFICATION SOIL TIGHT INTEGRAL BELL PIPE SHALL HAVE A SMOOTH Α. INTERIOR AND ANNULAR EXTERIOR CORRUGATIONS. 4- THROUGH10-INCH SHALL MEET AASHTO M252, TYPE S OR SP. 12- THROUGH 60-INCH SHALL MEET AASHTO M294, TYPE S OR SP OR ASTM F2306.
- в JOINT PERFORMANCE - PIPE SHALL BE JOINED USING A BELL & SPIGOT JOINT MEETING AASHTO M252, AASHTO M294 OR ASTM F2306. THE JOINT SHALL BE SOIL-TIGHT AND GASKETS, WHEN APPLICABLE, SHALL MEET THE REQUIREMENTS OF ASTM F477. GASKETS SHALL BE INSTALLED BY THE PIPE MANUFACTURER AND COVERED WITH A REMOVABLE WRAP TO ENSURE THE GASKET IS FREE FROM DEBRIS. A JOINT LUBRICANT SUPPLIED BY THE MANUFACTURER SHALL BE USED ON THE GASKET AND BELL DURING ASSEMBLY.
- C. FITTINGS FITTINGS SHALL CONFORM TO AASHTO M252, AASHTO M294, OR ASTM F2306. BELL AND SPIGOT CONNECTIONS SHALL UTILIZE A SPUN-ON OR WELDED BELL AND VALLEY OR SADDLE GASKET MEETING THE SOIL-TIGHT JOINT PERFORMANCE REQUIREMENTS OF AASHTO M252, AASHTO M294 OR ASTM F2306.

UTILITY NOTES:

- SEWER SERVICES:
- 1. ALL SANITARY SEWER SERVICE CONSTRUCTION SHALL COMPLY WITH THE LATEST EDITION OF THE NORTH CAROLINA BUILDING CODE - PLUMBING CODE. IT IS THE CONTRACTOR'S RESPONSIBILITY TO OBTAIN A PLUMBING PERMIT FROM HIGH POINT BUILDING INSPECTIONS
- WATER / SEWER / STORM SEPARATION VERIFICATION:
- 2. SEE AS-BUILT NOTES ON THIS SHEET FOR REQUIRED UTILITY AS-BUILT INFO DURING & POST-CONSTRUCTION. REQUIRED SEPARATIONS ARE AS FOLLOWS (UNLESS OTHERWISE NOTED:
- MINIMUM VERTICAL SEPARATION REQUIREMENTS: SANITARY - STORM: 24" SANITARY - WATER: 18"
- SANITARY OTHER UTILITIES: 24"
- WATER STORM: 18"
- CITY OF HIGH POINT REQUIREMENTS: 3. CONTACT THE CITY OF HIGH POINT ENGINEERING SERVICES DEPARTMENT, CONSTRUCTION INSPECTIONS DIVISION (336) 883-3194, AND THE ENGINEER FOR A PRE-CONSTRUCTION MEETING PRIOR TO BEGINNING INSTALLATION OF WATER AND SEWER MAINS, WATER AND SEWER SERVICE TAPS, STORM DRAINAGE, SIDEWALKS, DRIVEWAYS, AND ROADWAY IMPROVEMENTS.
- 4. ALL EXISTING SEWER MANHOLE MODIFICATIONS SHALL BE COORDINATED AND INSPECTED BY THE CITY ENGINEERING SERVICES DEPARTMENT INSPECTOR.
- 5. UPON COMPLETION OF THE PROJECT, AS-BUILT DRAWINGS OF THE WATER, SEWER, ROADWAY AND STORM DRAINAGE SYSTEMS SHALL BE SUBMITTED TO THE CITY ENGINEERING SERVICES DEPARTMENT. AS-BUILTS SHALL INCLUDE WATER METER AND SEWER CLEANOUT LOCATIONS. SEE UTILITY SHEETS FOR AS-BUILT REQUIREMENTS.
- 6. FIRE MAINS AND FIRE HYDRANTS SHALL BE INSTALLED, TESTED AND FUNCTIONAL BEFORE COMBUSTIBLE BUILDING MATERIALS ARE BROUGHT TO THE SITE PER FIRE CODE SECTION 1412.1.

OTHER REQUIREMENTS:

- 7. CLEAN-OUTS, VAULTS, METERS, BACKFLOW PREVENTERS AND ALL OTHER UTILITY STRUCTURES INSTALLED IN PAVED AREAS SHALL BE TRAFFIC RATED.
- 8. CONTRACTOR TO PROVIDE CONDUIT FOR SITE LIGHTING IN ACCORDANCE WITH CITY OF HIGH OF HIGH POINT STANDARDS. CONTRACTOR TO COORDINATE DIRECTLY WITH THE CITY OF HIGH POINT FOR LOCATION AND ROUTING OF CONDUIT.
- 9. CONTRACTOR SHALL COORDINATE DIRECTLY WITH THE CITY OF HIGH POINT AND ELECTRICAL ENGINEER PRIOR TO CONSTRUCTION FOR FINAL ELECTRICAL CONDUIT ROUTING; # & SIZE OF CONDUITS; AND PULL BOX LOCATIONS.

RETAINING WALL APPEARANCE SPECIFICATIONS:

- RETAINING WALLS SHALL BE DESIGNED AND CERTIFIED BY A PROFESSIONAL ENGINEER LICENSED IN THE STATE OF NORTH CAROLINA. RETAINING WALLS ARE INDICATED ON THESE PLANS FOR GENERAL LAYOUT AND SITE GRADING PURPOSES ONLY. FINAL DESIGN BY OTHERS.
- 2. RETAINING WALL SHALL BE DESIGNED, FURNISHED, AND CONSTRUCTED IN ACCORDANCE WITH THE MANUFACTURES SPECIFICATIONS.
- 3. CONTRACTOR SHALL SUBMIT CUT SHEETS, SHOP DRAWINGS, COLOR OPTIONS, AND CAP OPTIONS TO THE OWNER AND CIVIL ENGINEER FOR APPROVAL PRIOR TO ORDERING MATERIALS.
- 4. RETAINING WALL UNIT APPEARANCE 4.1. FACE COLOR SHALL BE NATURAL OR TAN.
- 4.2. FACE FINISH SHALL BE OF STRAIGHT FACE CONFIGURATION WITH MINIMUM CHISELING. 4.3. WALL BATTER SHALL BE MINIMUM AS DIRECTED BY THE WALL DESIGNER.
- 4.4. UNIT SIZE SHALL HAVE A MAXIMUM DEPTH OF 12-INCHES DUE TO HORIZONTAL SITE CONSTRAINTS.

SUBMITTALS:

SUBMITTALS ARE REQUIRED FOR THE FOLLOWING AREAS OF WORK PRIOR TO ORDERING ANY MATERIALS

STORM DRAINAGE PIPE

- DRAINAGE STRUCTURES FRAMES, GRATES AND COVERS
- SANITARY SEWER PIPE
- MANHOLES

WATER DISTRIBUTION PIPE

- FITTINGS
- VAULTS RESTRAINT SYSTEMS

- MIX DESIGN FOR CONCRETE PAVING
- MIX DESIGN FOR CONCRETE SIDEWALK MIX DESIGN FOR CONCRETE CURB & GUTTER
- MIX DESIGN FOR ALL GRADES OF ASPHALT PAVING

• CUT SHEETS

- SHOP DRAWINGS
- COLOR OPTIONS CAP OPTIONS

<u>LIGHTING</u>



NCBEES CERT. NO.: C-1347

PRELIMINARY DRAWING NOT FOR CONSTRUCTIO

PROJECT:

CLIENT:

DRAWN:

DATE

CITY OF HIGH POINT 211 S HAMILTON STREET HIGH POINT, NC 27260 (336) 883-8515

BWC

5/20/19

	0/20/10
REVISIONS:	
JOB. NO:	18-330
SHEET TITLE:	
	_
PROJEC	
	-
NOTES	
SCALE:	
SHEET NO ·	
SHEET NO.	
	1
© STIMMEL ASSOCIA	TES PA

CLEARING, EROSION & SEDIMENT CONTROL NOTES:

- 1. SEE EROSION CONTROL PLAN FOR DISTURBED AREA
- 2. A GRADING PERMIT SHALL BE OBTAINED FROM NCDEQ PRIOR TO ANY LAND DISTURBING ACTIVITY ON THE SITE.
- 3. CLEARING LIMITS SHALL BE CLEARLY DEFINED PRIOR TO BEGINNING CLEARING OPERATIONS. CLEARING DEBRIS SHALL BE PROPERLY DISPOSED OF OFFSITE IN A PERMITTED LANDFILL FACILITY, OR BY OTHER PERMITTED METHODS. TREES OUTSIDE THE CLEARING LIMITS SHALL BE PROTECTED DURING CONSTRUCTION. BURNING IS NOT ALLOWED ON THE SITE.
- 4. THE EROSION AND SEDIMENTATION CONTROL PLAN IS INTENDED AS A GUIDE TO INDICATE MINIMUM MEASURES TO BE TAKEN. AFTER GRADING BEGINS. ADDITIONAL MEASURES MAY BE NECESSARY TO CONTROL SEDIMENTATION AND EROSION ONSITE. IF SO, ADDITIONAL MEASURES SHALL BE INSTALLED AS DIRECTED BY NCDEQ EROSION CONTROL INSPECTOR.
- 5. ALL EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE NCDEQ - LAND QUALITY SECTION'S EROSION AND SEDIMENT CONTROL PLANNING AND DESIGN MANUAL.
- 6. THE NORTH CAROLINA SEDIMENTATION POLLUTION CONTROL PROGRAM REQUIRES GROUND COVER TO BE PROVIDED WITHIN VARYING TIME FRAMES BASED ON COMPLETION OF PHASES OF GRADING OR TOTAL PROJECT COMPLETION. GROUND STABILIZATION REQUIREMENTS ARE AS FOLLOWS:
- PERIMETER DIKES, SWALES, DITCHES AND SLOPES SHALL BE STABILIZED WITHIN 7 DAYS OF COMPLETION. • SLOPES STEEPER THAN 3:1 SHALL BE STABILIZED WITHIN 7 DAYS. IF SLOPES ARE 10' OR LESS IN LENGTH AND NOT STEEPER THAN 2:1, STABILIZATION IS REQUIRED WITHIN 14 DAYS. • SLOPES 3:1 OR FLATTER SHALL BE STABILIZED WITHIN 14 DAYS. IF SLOPES EXCEEDS 50' IN LENGTH, STABILIZATION IS REQUIRED WITHIN 7 DAYS
- ALL OTHER AREAS WITH SLOPES FLATTER THAN 4:1 SHALL BE STABILIZED WITHIN 14 DAYS. 7. ALL SLOPE SURFACES SHALL BE ROUGHENED USING TRACKED EQUIPMENT TO MINIMIZE EROSION UNTIL SEEDING IS DONE.
- 8. CONTRACTOR IS RESPONSIBLE FOR ALL EROSION CONTROL PRACTICES REQUIRED TO MINIMIZE EFFECTS ON ADJACENT PROPERTIES DURING CONSTRUCTION. EROSION CONTROL PRACTICES SHALL BE CONSTUCTED IN ACCORDANCE WITH DETAILS AND ARE TO BE MAINTAINED UNTIL CONTRIBUTING AREAS ARE STABLE.
- 9. PROPERTY OWNER IS RESPONSIBLE FOR ALL PERMANENT MEASURES AFTER CONSTRUCTION IS COMPLETE AND CONTRACTOR IS RELEASED.
- 10. ALL DISTURBED AREAS NOT OTHERWISE DELINEATED FOR BUILDING, PAVING, SOD, STONE, OR RIPRAP SHALL BE PERMANENTLY SEEDED AS SOON AS POSSIBLE IN ACCORDANCE WITH PERMANENT SEEDING SPECIFICATIONS SHOWN ON THE PLANS.
- 11. INSPECT AND REPAIR ALL EROSION CONTROL DEVICES ON A WEEKLY BASIS AND INSPECT AND REPAIR IMMEDIATELY FOLLOWING ANY RAINFALL
- 12. ANY REQUIRED BORROW FILL MATERIAL SHALL COME FROM A SITE THAT IS COVERED UNDER AN ACTIVE EROSION CONTROL PERMIT. ANY EXCESS SOIL MATERIAL TO BE WASTED OFF-SITE SHALL BE WASTED ON A SITE THAT IS COVERED UNDER AN ACTIVE EROSION CONTROL PERMIT. THE CONTRACTOR SHALL PROVIDE THE PERMIT NUMBER OF ALL BORROW AND WASTE SITES TO BE USED TO THE OWNER & EROSION CONTROL INSPECTOR.
- 13. ANY SOIL STOCKPILE AREAS SHALL BE GRADED TO DRAIN AND COMPACTED TO PREVENT SOIL FROM BECOMING SATURATED AND SHALL BE LOCATED ON SITE SUCH THAT THEY DRAIN TO AN APPROVED EROSION CONTROL MEASURE.
- 14. NO CLEARING OR GRADING WORK SHALL COMMENCE UNTIL SEDIMENTATION AND EROSION CONTROL PLAN APPROVAL AND GRADING PERMIT HAS BEEN ISSUED. INITIAL CLEARING SHALL BE LIMITED TO WHAT IS NECESSARY TO INSTALL THE EROSION CONTROL MEASURES. AFTER ALL EROSION CONTROL MEASURES ARE IN PLACE AND FUNCTIONING, THE REMAINING SITE AREAS MAY BE CLEARED AND GRUBBED
- 15. THE DISPOSAL OF DEBRIS IS NOT ALLOWED ON SITE
- 16. PROTECTION OF EXISTING TREES AND COMMON AREAS TO BE ACCOMPLISHED WITH TREE PROTECTION FENCE AS SHOWN ON THE PLANS & DETAILS. THE ENCROACHMENT PROTECTION MEASURES SHALL BE PROPERLY MAINTAINED DURING SITE DEVELOPMENT AND SHALL NOT BE REMOVED PRIOR TO FINAL LANDSCAPING.
- 17. ALL TEMPORARY EROSION CONTROL DEVICES SHALL BE REMOVED AT THE END OF CONSTRUCTION AND WHEN APPROVED BY THE EROSION CONTROL INSPECTOR UNLESS SPECIFICALLY NOTED TO REMAIN AS PERMANENT. REMOVAL SHALL INCLUDE REMOVAL AND DISPOSAL OF SEDIMENT, ALL NECESSARY FILLING, GRADING, REMOVING MATERIALS, FERTILIZATION, SEEDING AND MULCHING, AND ESTABLISHING VEGETATION.

GENERAL SEQUENCE OF CONSTRUCTION

- 1. OBTAIN GRADING/EROSION CONTROL PLAN APPROVAL AND PERMIT FROM NCDEQ.
- 2. CONTRACTOR SHALL CONTACT EROSION CONTROL INSPECTOR TO SCHEDULE A PRE-CONSTRUCTION CONFERENCE. IN ADDITION, CONTRACTOR MUST PERFORM SELF INSPECTIONS IN ACCORDANCE WITH THE "SELF INSPECTION REQUIREMENTS" ON THESE PLANS.
- 3. CLEAR SITE ONLY AS NECESSARY TO INSTALL INITIAL EROSION CONTROL MEASURES AS FOLLOWS: a. TEMPORARY CONSTRUCTION ENTRANCE/EXIT b. TEMPORARY SEDIMENT BASINS. FOR SITES OVER ONE (1) ACRE, OUTLET STRUCTURES [SKIMMERS] THAT ONLY WITHDRAW WATER FROM THE SURFACE OF THE BASIN, SHALL BE UTILIZED. NO SEDIMENT TRAPS OR ROCK DAMS ALLOWED. . TEMPORARY DIVERSION BERMS d. TEMPORARY SILT FENCING. SEED EMBANKMENTS AND DISTURBED AREAS OF DEVICES (INCLUDING "CLEAN" WATER DIVERSION) UPON
- COMPLETION OF CONSTRUCTION. SEE GROUND STABILIZATION CRITERIA BELOW FOR MORE INFORMATION. 4. BEGIN CLEARING, GRUBBING AND STRIPPING OF SITE AS REQUIRED. MATERIAL STOCKPILES, AREAS DEDICATED FOR MANAGEMENT OF LAND CLEARING AND DEMOLITION DEBRIS, AND CONSTRUCTION WASTE SHALL BE LOCATED AT LEAST 50 FEET FROM STORM DRAIN INLETS AND
- BEGIN SITE GRADING. MAINTAIN EROSION CONTROL DEVICES IN ACCORDANCE WITH THE MAINTENANCE PLAN. INSTALL ADDITIONAL EROSION CONTROL MEASURES AS REQUIRED.

BY EROSION CONTROL MEASURES.

- 6. INSTALL STORM DRAINAGE SYSTEM AND UTILITIES. STORM PIPING SHALL BE INSTALLED TO THE POINT WHERE IT ENTERS EACH DEVICE. COMPLETION OF PIPING WILL ONLY BE ALLOWED ONCE THE SITE HAS BEEN DEEMED STABLE BY THE EROSION CONTROL INSPECTOR. INSTALL PROTECTION AROUND ALL INLETS AS STORM DRAIN SYSTEM IS INSTALLED.
- 7. CONTINUE TO MAINTAIN EROSION CONTROL MEASURES UNTIL VEGETATIVE COVER HAS BEEN ESTABLISHED OVER ALL DISTURBED AREAS AND SITE HAS BEEN STABILIZED. REMOVE EROSION CONTROL MEASURES ONLY AFTER FINAL INSPECTION AND APPROVAL BY INSPECTOR.
- 8. SEE EROSION CONTROL PLAN DRAWINGS FOR STAGE SPECIFIC SEQUENCE OF CONSTRUCTION AND NOTES.

SURFACE WATERS (UNLESS IT CAN BE SHOWN THAT NO OTHER ALTERNATIVES ARE REASONABLY AVAILABLE), AND WITHIN AREAS PROTECTED

MAINTENANCE PLAN:

EMPORARY GRAVEL CONSTRUCTION ENTRANCE MAINTAIN THE GRAVEL PAD IN A CONDITION TO PREVENT MUD OR SEDIMENT FROM LEAVING THE CONSTRUCTION SITE. THIS MAY REQUIRE PERIODIC TOPDRESSING WITH 2-INCH STONE. AFTER EACH RAINFALL, INSPECT ANY STRUCTURE USED TO TRAP SEDIMENT AND CLEAN IT OUT AS NECESSARY. IMMEDIATELY REMOVE ALL OBJECTIONABLE MATERIALS SPILLED, WASHED, OR TRACKED ONTO PUBLIC ROADWAYS.

TEMPORARY SEEDING RESEED AND MULCH AREAS WHERE SEEDLING EMERGENCE IS POOR, OR WHERE EROSION OCCURS, AS SOON AS POSSIBLE. DO NOT MOW. PROTECT FROM TRAFFIC AS MUCH AS POSSIBLE.

TEMPORARY DIVERSIONS INSPECT TEMPORARY DIVERSIONS ONCE A WEEK AND AFTER EVERY RAINFALL. IMMEDIATELY REMOVE SEDIMENT FROM THE FLOW AREA AND REPAIR THE DIVERSION RIDGE. CAREFULLY CHECK OUTLETS AND MAKE TIMELY REPAIRS AS NEEDED. WHEN THE PROTECTED AREA IS PERMANENTLY STABILIZED, REMOVE THE RIDGE AND THE CHANNEL TO BLEND WITH THE NATURAL GROUND LEVEL AND APPROPRIATELY STABILIZE IT.

TEMPORARY SLOPE DRAINS INSPECT THE SLOPE DRAIN AND SUPPORTING DIVERSION AFTER EVERY RAINFALL AND PROMPTLY MAKE NECESSARY REPAIRS. WHEN THE PROTECTED AREA HAS BEEN PERMANENTLY STABILIZED, TEMPORARY MEASURES MAY BE REMOVED, MATERIALS DISPOSED OF PROPERLY, AND ALL DISTURBED AREAS STABILIZED APPROPRIATELY. **RIP RAP OUTLET PROTECTION**

INSPECT RIPRAP OUTLET STRUCTURES AFTER HEAVY RAINS TO SEE IF ANY EROSION AROUND OR BELOW THE RIPRAP HAS TAKEN PLACE OR IF STONES HAVE BEEN DISLODGED. IMMEDIATELY MAKE ALL NEEDED REPAIRS TO PREVENT FURTHER DAMAGE.

SEDIMENT BASINS CHECK SEDIMENT BASINS AFTER PERIODS OF SIGNIFICANT RUNOFF. REMOVE SEDIMENT AND RESTORE THE BASIN TO ITS ORIGINAL DIMENSIONS WHEN SEDIMENT ACCUMULATES TO ONE-HALF THE BAFFLE HEIGHT OF THE FIRST BAFFLE. CHECK THE EMBANKMENT, SPILLWAYS, AND OUTLET FOR EROSION DAMAGE, AND INSPECT THE EMBANKMENT FOR PIPING AND SETTLEMENT. MAKE ALL NECESSARY REPAIRS IMMEDIATELY. REMOVE ALL TRASH AND OTHER DEBRIS FROM THE RISER AND POOL AREA.

KIMMER BASIN

INSPECT SKIMMER SEDIMENT BASINS AT LEAST WEEKLY AND AFTER EACH SIGNIFICANT (ONE-HALF INCH OR GREATER) RAINFALL EVENT AND REPAIR IMMEDIATELY. REMOVE SEDIMENT AND RESTORE THE BASIN TO ITS ORIGINAL DIMENSIONS WHEN SEDIMENT ACCUMULATES TO ONE-HALF THE HEIGHT OF THE FIRST BAFFLE. PULL THE SKIMMER TO ONE SIDE SO THAT THE SEDIMENT UNDERNEATH IT CAN BE EXCAVATED. EXCAVATE THE SEDIMENT FROM THE ENTIRE BASIN, NOT JUST AROUND THE SKIMMER OR THE FIRST CELL. MAKE SURE VEGETATION GROWING IN THE BOTTOM OF THE BASIN DOES NOT HOLD DOWN THE SKIMMER.

REPAIR THE BAFFLES IF THEY ARE DAMAGED. RE-ANCHOR THE BAFFLES IF WATER IS FLOWING UNDERNEATH OR AROUND THEM

IF THE SKIMMER IS CLOGGED WITH TRASH AND THERE IS WATER IN THE BASIN, USUALLY JERKING ON THE ROPE WILL MAKE THE SKIMMER BOB UP AND DOWN AND DISLODGE THE DEBRIS AND RESTORE FLOW. IF THIS DOES NOT WORK PULL THE SKIMMER OVER THE SIDE OF THE BASIN AND REMOVE THE DEBRIS. ALSO CHECK THE ORIFICE INSIDE THE SKIMMER TO SEE IF IT IS CLOGGED; IF SO REMOVE THE DEBRIS.

IF THE SKIMMER ARM OR BARREL PIPE IS CLOGGED, THE ORIFICE CAN BE REMOVED AND THE OBSTRUCTION CLEARED WITH A PLUMBER'S SNAKE OR BY FLUSHING WITH WATER. BE SURE TO REPLACE THE ORIFICE BEFORE REPOSITIONING THE SKIMMER.

CHECK THE FABRIC LINED SPILLWAY FOR DAMAGE AND MAKE ANY REQUIRED REPAIRS WITH FABRIC THAT SPANS THE FULL WIDTH OF THE SPILLWAY. CHECK THE EMBANKMENT, SPILLWAYS, AND OUTLET FOR EROSION DAMAGE. AND INSPECT THE EMBANKMENT FOR PIPING AND SETTLEMENT, MAKE ALL NECESSARY REPAIRS IMMEDIATELY REMOVE ALL TRASH AND OTHER DEBRIS FROM THE SKIMMER AND POOL AREAS.

FREEZING WEATHER CAN RESULT IN ICE FORMING IN THE BASIN. SOME SPECIAL PRECAUTIONS SHOULD BE TAKEN IN THE WINTER TO PREVENT THE SKIMMER FROM PLUGGING WITH ICE.

INSPECT SEDIMENT FENCES AT LEAST ONCE A WEEK AND AFTER EACH RAINFALL. MAKE ANY REQUIRED REPAIRS IMMEDIATELY, SHOULD THE FABRIC OF A SEDIMENT FENCE COLLAPSE, TEAR, DECOMPOSE OR BECOME INEFFECTIVE, REPLACE IT PROMPTLY, REPLACE BURLAP EVERY 60 DAYS, REMOVE SEDIMENT DEPOSITS AS NECESSARY TO PROVIDE ADEQUATE STORAGE VOLUME FOR THE NEXT RAIN AND TO REDUCE PRESSURE ON THE FENCE. TAKE CARE TO AVOID UNDERMINING THE FENCE DURING CLEANOUT. REMOVE ALL FENCING MATERIALS AND UNSTABLE SEDIMENT DEPOSITS AND BRING THE AREA TO GRADE AND STABILIZE IT AFTER THE CONTRIBUTING DRAINAGE AREA HAS BEEN PROPERLY STABILIZED.

PERMANENT GROUND COVER THE OWNER OR RESPONSIBLE PARTY IS RESPONSIBLE FOR THE LONG-TERM MAINTENANCE OF THE GROUNDCOVER ON THE PROPERTY, GROUNDCOVER MUST BE MAINTAINED TO A DEGREE THAT PREVENTS SOIL EROSION AND SEDIMENTATION AT ALL TIMES. NCDENR HAS THE AUTHORITY TO REQUIRE CHANGES IN THE OWNER'S GROUNDCOVER MAINTENANCE PLAN IN ORDER TO STOP SOIL EROSION AND SEDIMENTATION AT ANY TIME.

NPDES STORMWATER NOTES:

THIS PROJECT IS SUBJECT TO THE REQUIREMENTS OUTLINED IN NORTH CAROLINA GENERAL STATUTE 143-215.1 GENERAL STORMWATER PERMIT

THIS GENERAL PERMIT IS APPLICABLE TO POINT SOURCE DISCHARGES OF STORMWATER FROM CONSTRUCTION ACTIVITIES DISTURBING ONE OR MORE ACRES OF LAND. THE SUBMISSION OF A PROPOSED EROSION AND SEDIMENTATION CONTROL PLAN TO THE DIVISION OF LAND RESOURCES OR DELEGATED LOCAL PROGRAM SHALL BE CONSIDERED TO TAKE THE PLACE OF A NOTICE OF INTENT FOR COVERAGE UNDER THIS GENERAL PERMIT FOR THOSE PROJECTS REQUIRING THIS PERMIT COVERAGE. COVERAGE UNDER THIS GENERAL PERMIT SHALL BECOME EFFECTIVE UPON ISSUANCE OF AN APPROVAL FOR THE EROSION AND SEDIMENTATION CONTROL PLAN BY THE LAND QUALITY SECTION OF THE DIVISION OF LAND RESOURCES OR DELEGATED LOCAL PROGRAM. APPROVAL OF THE EROSION AND SEDIMENTATION CONTROL PLAN SHALL BE OBTAINED PRIOR TO THE COMMENCEMENT OF CONSTRUCTION AND I AND DISTURBING ACTIVITIES

ALL EROSION AND SEDIMENTATION CONTROL FACILITIES SHALL BE INSPECTED BY OR UNDER THE DIRECTION OF THE PERMITTEE AT LEAST ONCE EVERY SEVEN CALENDAR DAYS (AT LEAST TWICE EVERY SEVEN DAYS FOR THOSE FACILITIES DISCHARGING TO WATERS OF THE STATE LISTED ON THE LATEST EPA APPROVED 303(D) LIST FOR CONSTRUCTION RELATED INDICATORS OF IMPAIRMENT SUCH AS TURBIDITY OR SEDIMENTATION) AND WITHIN 24 HOURS AFTER ANY STORM EVENT OF GREATER THAT 0.5 INCHES OF RAIN PER 24 HOUR PERIOD. A RAIN GAUGE SHALL BE MAINTAINED ON THE SITE AND A RECORD OF THE RAINFALL AMOUNTS AND DATES SHALL BE KEPT BY THE PERMITTEE. REFER TO THE GENERAL STORMWATER PERMIT FOR A COMPLETE LIST OF INSPECTION AND REPORTING REQUIREMENTS.

A COPY OF THIS PERMIT IS ATTACHED TO THE APPROVED PERMIT OR IT CAN BE DOWNLOADED FROM NCDENR'S WEBSITE.

SELF INSPECTION REQUIREMENTS

THIS PROJECT IS SUBJECT TO THE REQUIREMENTS OUTLINED IN NORTH CAROLINA GENERAL STATUTE 113A-54.1(E) AND IN THE NC ADMINISTRATIVE CODE 15A NCAC 04B .0131, SELF-INSPECTIONS.

THE SELF-INSPECTION PROGRAM IS SEPARATE FROM THE WEEKLY SELF-MONITORING PROGRAM OF THE NPDES STORMWATER PERMIT FOR CONSTRUCTION ACTIVITIES. THE FOCUS OF THE SELF-INSPECTION REPORT IS THE INSTALLATION AND MAINTENANCE OF EROSION AND SEDIMENTATION CONTROL MEASURES ACCORDING TO THE APPROVED PLAN. THE INSPECTIONS SHOULD BE CONDUCTED AFTER EACH PHASE OF THE PROJECT, AND CONTINUED UNTIL PERMANENT GROUND COVER IS ESTABLISHED.

- THE CONTRACTOR SHALL PERFORM THE REQUIRED SELF-INSPECTIONS AT THE COMPLETION OF EACH PHASE OF CONSTRUCTION AND COMPLETE THE STANDARD NCDEQ SELF INSPECTION FORMS INCLUDED IN THE GRADING PERMIT APPROVAL. THE PHASES ARE AS FOLLOWS:
- INSTALLATION OF PERIMETER EROSION AND SEDIMENT CONTROL MEASURES. CLEARING AND GRUBBING OF EXISTING GROUND COVER.
- COMPLETION OF ANY PHASE OF GRADING OF SLOPES OR FILLS. INSTALLATION OF STORM DRAINAGE FACILITIES.
- COMPLETION OF CONSTRUCTION OR DEVELOPMENT.
- ESTABLISHMENT OF PERMANENT GROUND COVER SUFFICIENT TO RESTRAIN EROSION.

THE INSPECTION SHALL VERIFY THAT ALL OF THE INSTALLED EROSION AND SEDIMENTATION CONTROL MEASURES, PRACTICES AND DEVICES ARE CONSISTENT WITH THE APPROVED EROSION AND SEDIMENTATION CONTROL PLAN AND ALL PREVIOUSLY CONSTRUCTED EROSION CONTROL MEASURES HAVE BEEN MAINTAINED IN ACCORDANCE WITH THE MAINTENANCE SCHEDULE.

IN ANY SIGNIFICANT DEVIATIONS FROM THE APPROVED EROSION AND SEDIMENTATION CONTROL PLAN ARE FOUND. THEN THE CONTRACTOR SHALL TAKE THE NECESSARY CORRECTIVE ACTIONS TO CORRECT THE DEVIATIONS. A SIGNIFICANT DEVIATION MEANS AN OMISSION, ALTERATION OR RELOCATION OF AN EROSION OR SEDIMENTATION CONTROL MEASURE THAT PREVENTS THE MEASURE FROM PERFORMING AS INTENDED.

STREET CLEANING:

ROADS SHALL BE KEPT CLEAN OF MUD, SEDIMENT AND OTHER CONSTRUCTION RELATED DEBRIS AT ALL TIMES DURING CONSTRUCTION OF THIS PROJECT. THIS MAY REQUIRE STREET SWEEPING AND ROUTINE WASHING AND

SHALL BE INCLUDED IN THE CONTRACTOR'S BID. CONTRACTOR TO PROVIDE MEANS TO PERFORM WHEEL WASHING.

DUST CONTROL

DUST CAN BE A SIGNIFICANT SOURCE OF AIR POLLUTION ON LARGE CONSTRUCTION SITES. DUST CONTROL MAY BECOME NECESSARY DURING THE PROJECT. SEVERAL METHODS ARE EFFECTIVE IN CONTROLLING DUST, HOWEVER THE MOST COMMON IS SPRINKLING ACCESS ROADS WITH WATER. ANOTHER IS USING STONE TO STABILIZE ACCESS ROADS. PROVIDE DUST CONTROL ON AN AS NEEDED BASIS.

USE OF FLOCCULANTS:

FLOCCULANTS ARE AN EFFECTIVE METHOD OF ENHANCING SETTLEMENT OF SUSPENDED SEDIMENT. PRODUCTS USING A CHEMICAL KNOWN AS POLYACRYLAMIDE (PAM) ARE SPECIFIED FOR THIS PROJECT. THESE PRODUCTS SHALL BE USED AND INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS. THE CONTRACTOR SHALL CONFIRM WITH THE VENDOR THAT PAM'S USED ON THE SITE COMPLY WITH THE CHRONIC TOXICITY TESTING REQUIREMENTS ESTABLISHED BY THE NC DIVISION OF WATER QUALITY. DO NOT APPLY PAM'S DIRECTLY TO 'SURFACE WATERS OF THE STATE'. SURFACE WATERS OF THE STATE INCLUDE STREAMS, PONDS AND OTHER WATER FEATURES THAT ARE OUTSIDE OF THE DISTURBED LIMITS OF THE SITE.

TEMPORARY SEEDING:

SEEDING SPECIFICATIONS APPLY 4000 LBS. AGRICULTURAL LIMESTONE PER ACRE. APPLY 1000 LBS. 10-10-10- FERTILIZER PER ACRE FOR GRASS SEEDING. LIME AND FERTILIZER ARE TO BE DISKED INTO THE SOIL SURFACE TO A MINIMUM DEPTH OF

4 INCHES.
FOR LATE WINTER/EARLY SPRING SEEDING MIXTURE SPECIES: RATE (LB/ACRE): RYE (GRAIN) 120 ANNUAL LESPEDEZA 50 (KOBE IN PIEDMONT & COASTAL PLAIN, KOREAN IN MOUNTAINS)
SEEDING DATES MOUNTAINSFEB. 1 - MAY 1 PIEDMONTJAN. 1 - MAY 1 COASTAL PLAINDEC. 1 - APR. 15
SOIL AMENDMENTS FOLLOW RECOMMENDATIONS OF SOIL TESTS OR APPLY 2,000 LB/ACRE GROUND AGRICULTURAL LIMESTONE AND 750 LB/ACRE 10-10-10 FERTILIZER.
MULCH APPLY 4,000 LB/ACRE STRAW. ANCHOR STRAW BY TACKING WITH ASPHALT, NETTING, OR A MULCH ANCHORING TOOL. A DISK WITH BLADES SET NEARLY STRAIGHT CAN BE USED AS A MULCH ANCHORING TOOL.
MAINTENANCE REFERTILIZE IF GROWTH IS NOT FULLY ADEQUATE. RESEED, REFERTILIZE AND MULCH IMMEDIATELY FOLLOWING EROSION OR OTHER DAMAGE.
FOR SUMMERSEEDING MIXTURESPECIES:RATE (LB/ACRE):GERMAN MILLET40
IN THE PIEDMONT AND MOUNTAINS, A SMALL-STEMMED SUDAN GRASS MAY BE SUBSTITUTED AT A RATE OF 50 LB/ACRE.
SEEDING DATES MOUNTAINSMAY 15 - AUG. 15 PIEDMONTMAY 1 - AUG. 15 COASTAL PLAINAPR. 15 - AUG. 15
SOIL AMENDMENTS FOLLOW RECOMMENDATIONS OF SOIL TESTS OR APPLY 2,000 LB/ACRE GROUND AGRICULTURAL LIMESTONE AND 750 LB/ACRE 10-10-10 FERTILIZER.
MULCH APPLY 4,000 LB/ACRE STRAW. ANCHOR STRAW BY TACKING WITH ASPHALT, NETTING, OR A MULCH ANCHORING TOOL. A DISK WITH BLADES SET NEARLY STRAIGHT CAN BE USED AS A MULCH ANCHORING TOOL.
MAINTENANCE REFERTILIZE IF GROWTH IS NOT FULLY ADEQUATE. RESEED, REFERTILIZE AND MULCH IMMEDIATELY FOLLOWING EROSION OR OTHER DAMAGE.
FOR FALLSEEDING MIXTURESPECIES:RATE (LB/ACRE):RYE (GRAIN)120
SEEDING DATES MOUNTAINSAUG. 15 - DEC. 15 PIEDMONT AND COASTAL PLAINAUG. 15 - DEC. 30
SOIL AMENDMENTS FOLLOW RECOMMENDATIONS OF SOIL TESTS OR APPLY 2,000 LB/ACRE GROUND AGRICULTURAL LIMESTONE AND 1,000 LB/ACRE 10-10-10 FERTILIZER.
MULCH APPLY 4,000 LB/ACRE STRAW. ANCHOR STRAW BY TACKING WITH ASPHALT, NETTING, OR A MULCH ANCHORING TOOL. A DISK WITH BLADES SET NEARLY STRAIGHT CAN BE USED AS A MULCH ANCHORING TOOL.
MAINTENANCE REPAIR AND REFERTILIZE DAMAGED AREAS IMMEDIATELY. TOPDRESS WITH 50 LB/ACRE OF NITROGEN IN MARCH. IF IT IS NECESSARY TO EXTEND TEMPORARY COVER BEYOND JUNE 15, OVERSEED WITH 50 LB/ACRE KOBE (PIEDMONT AND COASTAL PLAIN) OR KOREAN

(MOUNTAINS) LESPEDEZA IN LATE FEBRUARY OR EARLY MARCH.

SEEDBED PREPARATION

- . RIP AREA TO BE SEEDED TO A MINIMUM DEPTH OF 4-6 INCHES. 2. REMOVE ALL LOOSE ROCKS, ROOTS, ETC. LEAVING SURFACE SMOOTH AND UNIFORM.
- 3. APPLY SEED, AGRICULTURAL LIME, FERTILIZER AND SUPER PHOSPHATE UNIFORMLY AND MIX WITH THE SOIL 4. SEED ON A FRESHLY PREPARED SEEDBED AND COVER THE SEED LIGHTLY WITH SEEDING
- EQUIPMENT OR CULTIPACK AFTER SEEDING. 5. MULCH IMMEDIATELY AFTER SEEDING AND ANCHOR MULCH.

AFTER SEEDING, THE AREA IS TO BE ROLLED OR CULTIPACKED TO INSURE THAT THE SEED IS PRESSED INTO CONTACT WITH SOIL SURFACE. ALL SEEDED AREAS ARE TO BE MULCHED WITH STRAW MULCH AT THE RATE OF 3000 LBS. PER ACRE. (APPX. 100 BALES PER ACRE.)

THE ABOVE SEEDING RECOMMENDATIONS AND RATES HAVE BEEN PREPARED FOR SELECTION OF A VEGETATIVE COVER SUITABLE FOR SOIL EROSION CONTROL IN THE DAVIE COUNTY AREA.

AREA SOIL TYPES, CLIMATIC CONDITIONS, SEED AVAILABILITY AND INDIVIDUAL PLANT CHARACTERISTICS ARE ALL TAKEN INTO ACCOUNT IN THE ABOVE RECOMMENDATIONS. DUE TO DENSITY, UNIFORMITY AND TEXTURAL QUALITY REASONS, THE ABOVE SELECTIONS ARE NOT RECOMMENDED FOR LAWN AREA USE.

PERMANENT SEEDING:

Planting Type	Planting Rates/ Acres	Planting Dates *
Blend of two turf-type tall fescues (90%) and two or more improved Kentucky bluegrass varieties (10%) high maintenance	200-250 lbs.	Aug. 15 -Oct. 15 Feb. 15 -May 1
* CONTRACTOR SHALL FOLLOW TEMPORA REQUIRED OUTSIDE OF THE PERMANENT	RY SEEDING SPECIFICATIONS WH	IEN PERMANENT SEEDING IS
PURPOSE TO PERMANENTLY STABILIZE DISTURBED ARE/ EROSION.	AS CREATED BY CONSTRUCTION A	ACTIVITIES AND MINIMIZE SOIL
PRACTICAL APPLICATIONS WHERE BARE SOIL ON CONSTRUCTION ACTIVI CONTROL MEASURES.	TIES IS NOT COVERED BY STRUCT	FURES OR OTHER EROSION
<u>PREPARATION</u> PREPARE SEEDBED BY RIPPING, CHISELING, H. LOOSE, FRIABLE SURFACE. REMOVE ALL STON WOULD PROHIBIT GERMINATION OR PLANT GR	ARROWING, OR PLOWING TO A DE IES, BOULDERS, STUMPS, OR DEB OWTH.	EPTH OF 6" THAT PRODUCES A RIS FROM THE SURFACE WHICH
INCORPORATE INTO THE SOIL 800-1000 IBS. OF ACRE AND 2 TONS OF DOLOMITIC LIME PER AC BE USED.	10-10-10 FERTILIZER PLUS 500 IB RE UNLESS SOIL TESTS INDICATE	S. OF 20% SUPERPHOSPHATE PER E THAT A LOWER RATE OF LIME CAN

MULCH AFTER SEEDING WITH 1.5 TONS OF GRAIN STRAW PER ACRE AND CRIMP STRAW INTO THE SOIL OR TACK WITH LIQUID ASPHALT AT 400 GALLONS PER ACRE OR EMULSIFIED ASPHALT AT 300 GALLONS PER ACRE.

ENVIRONMENTAL NOTES

REFER TO THE ENVIRONMENTAL MANAGEMENT PLAN PREPARED BY ECS, LTD FOR REQUIREMENTS RELATED TO THE CONSTRUCTION ACTIVITIES AND THE ONSITE CONTAMINATION.



NCBEES CERT. NO.: C-1347

PRFI IMINAR DRAWING

PROJECT:



CLIENT:

CITY OF HIGH POINT 211 S HAMILTON STREET HIGH POINT, NC 27260 (336) 883-8515

BWC
5/20/19

18-330

JOB. NO: SHEET TITLE: PROJEC



STIMMEL:



PARKING NUMBER

DETAIL BUBBLE

SITE:



HANDICAP SPACE HANDICAP SIGN CURB STOP BOLLARD SITE LIGHTING

DEMO:

	CURBING TO BE REMOVED
<i># # # # # # # #</i>	ASPHALT SAW CUT LINE
-000	FENCING TO BE REMOVED
	EXISTING BUILDING TO BE REMOVED
	EXISTING CONCRETE TO BE REMOVED
	EXISTING ASPHALT TO BE REMOVED

HATCHES:



WETLANDS PROPOSED CONCRETE PAVING PROPOSED LIGHT DUTY ASPHALT PAVING PROPOSED HEAVY DUTY ASPHALT PAVING

EXISTING GRADING & EC:

\bigcirc	EXISTING DRAINAGE MANHOLE
	EXISTING CURB INLET
	EXISTING GRATE INLET
	EXISTING YARD INLET
	EXISTING FLARED END STATION

PROPOSED GRADING & EC:

Θ	PROPOSED DRAINAGE MANHOLE
	PROPOSED CURB INLET 'TYPE E'
	PROPOSED GRATE INLET
	PROPOSED YARD INLET
(b)	PROPOSED SURFACE DRAIN INLET
	PROPOSED TRENCH DRAIN
	PROPOSED FLARED END SECTION
	PROPOSED CHECK DAM
	PROPOSED TERRA TUBE
	PROPOSED SILT FENCE STONE OUTLET
	PROPOSED SILT FENCE TERRA TUBE OUTLET
	PROPOSED FLOC LOG
\bigcirc	PROPOSED WIRE & GRAVEL INLET PROTECTION
0	PROPOSED STONE DOUGHNUT INLET PROTECTION
	PROPOSED SLOPE DRAIN
G	PROPOSED SKIMMER OUTLET
	PROPOSED RIPRAP OUTLET PAD

EXISTING WATER & SEWER:



- EXISTING GATE VALVE
- EXISTING FIRE HYDRANT
- EXISTING SANITARY SEWER MANHOLE
- EXISTING CLEANOUT

PROPOSED WATER & SEWER:



PROPOSED 45° BEND PROPOSED 90° BEND

PROPOSED 22.5° BEND

- PROPOSED CROSS
- PROPOSED FDC
- PROPOSED GATE VALVE
- PROPOSED FIRE HYDRANT
- PROPOSED PLUG
- PROPOSED REDUCER
- PROPOSED TAPPING SLEEVE
- PROPOSED TEE
- PROPOSED SANITARY SEWER MANHOLE
 - PROPOSED SANITARY CLEANOUT

SITE:

-0-0-0-00
cc
——————————————————————————————————————
UGE
OHE
G
CTV
FOC

PROPERTY BOUNDARY PROPOSED BUILDING RIGHT OF WAY PROPOSED CENTERLINE PROPOSED CURB AND GUTTER PROPOSED FENCE PROPOSED TREE LINE/CLEARING LIMITS GUARDRAIL CONDUIT **EXISTING CURB & GUTTER** EXISTING CENTERLINE EXISTING ELECTRIC LINE EXISTING UNDERGROUND ELECTRIC LINE EXISTING OVERHEAD ELECTRIC LINE EXISTING GAS LINE EXISTING CABLE TV LINE EXISTING FIBER OPTIC CABLE EXISTING TREE LINE

PROPOSED MAJOR CONTOURS

PROPOSED MINOR CONTOURS

PROPOSED ROOF LEADER

EXISTING MAJOR CONTOURS

EXISTING MINOR CONTOURS

LIMITS OF DISTURBANCE

TREE PROTECTION FENCE

DIVERSION BERM FLOW / SWALE LINE

SILT FENCE

EXISTING STORM DRAINAGE LINE

PROPOSED STORM DRAINAGE LINE

GRADING & EROSION CONTROL:



WATER & SEWER:



ENCROACHMENT FENCE PROPOSED IRRIGATION WATERLINE

PROPOSED SANITARY SEWER SERVICE



NCBEES CERT. NO.: C-1347

PRELIMINARY DRAWING NOT FOR CONSTRUCTION

PROJECT:



SNC OINT Δ Т HIGH

CLIENT:

CITY OF HIGH POINT 211 S HAMILTON STREET HIGH POINT, NC 27260 (336) 883-8515

DRAWN:	BWC
DATE:	5/20/19
REVISIONS:	
JOB. NO:	18-330
SHEET TITLE:	
LEGEND	
CHEET	
SHLLI	
SCALE:	
SHEET NU .:	
し-U.U)

© STIMMEL ASSOCIATES, P.A.





stimme LANDSCAPE ARCHITECTURE CIVIL ENGINEERING LAND PLANNING 601 N. TRADE STREET, SUITE 200 WINSTON-SALEM, NC 27101 P: 336.723.1067 F: 336.723.1069 www.stimmelpa.com SEALS: NCBEES CERT. NO.: C-1347

PRELIMINARY DRAWING NOT FOR CONSTRUCTION

PROJECT:

 \mathbf{O} Ž

CLIENT:

 \geq

U

Ζ

CITY OF HIGH POINT 211 S HAMILTON STREET HIGH POINT, NC 27260 (336) 883-8515



© STIMMEL ASSOCIATES, P.A.





PAVING SCHEDULE

NOTES:



Š D N C SNO Ω Δ AP НО Т

CLIENT:

CITY OF HIGH POINT 211 S HAMILTON STREET HIGH POINT, NC 27260 (336) 883-8515

BWC/JMT DRAWN: DATE: 5/20/19 **REVISIONS**: 18-330 JOB. NO: SHEET TITLE:

HARDSCAPE ENLARGEMENT PLANS

30

SCALE: 1" = 10'

North

stimmel LANDSCAPE ARCHITECTURE **CIVIL ENGINEERING** LAND PLANNING 601 N. TRADE STREET, SUITE 200 WINSTON-SALEM, NC 27101 P: 336.723.1067 F: 336.723.1069 www.stimmelpa.com SEALS:

NCBEES CERT. NO.: C-1347

PRELIMINARY DRAWING NOT FOR CONSTRUCTION

PROJECT:

 \geq \mathbf{O} Ž

U

Ζ

Ω

CLIENT:

CITY OF HIGH POINT 211 S HAMILTON STREET HIGH POINT, NC 27260 (336) 883-8515

© STIMMEL ASSOCIATES, P.A.

S

 \overline{O}

BWC

5/20/19

18-330

1. REFER TO SHEETS C-0.01 AND C-0.02 FOR ADDITIONAL NOTES. 2. REFER TO SHEETS C-3.20 AND C-6.10 FOR ADDITIONAL STORM DRAINAGE

INFORMATION AND DETAILS. 3. REFER TO SHEETS C-4.01 AND C-6.20 FOR ADDITIONAL UTILITY INFORMATION AND DETAILS.

stimme LANDSCAPE ARCHITECTURE CIVIL ENGINEERING LAND PLANNING 601 N. TRADE STREET, SUITE 200 WINSTON-SALEM, NC 27101 P: 336.723.1067 F: 336.723.1069 www.stimmelpa.com SEALS:

NCBEES CERT. NO.: C-1347

PRELIMINARY DRAWING NOT FOR CONSTRUCTION

PROJECT:

S \overline{O}

CLIENT:

J

3

U

Ζ

Ω

Ω

CITY OF HIGH POINT 211 S HAMILTON STREET HIGH POINT, NC 27260 (336) 883-8515

BWC DRAWN: DATE: 5/20/19 **REVISIONS:**

18-330

JOB. NO: SHEET TITLE:

OVERALL UTILITY PLAN

SCALE: 1" = 20' SHEET NO .:

© STIMMEL ASSOCIATES, P.A.

BWC

5/20/19

18-330

920

915

910

905

900

895

920

- REFER TO SHEETS C-0.01 AND C-0.02 FOR ADDITIONAL NOTES. 2. REFER TO SHEETS C-3.20, C-6.10 & C-6.11 FOR ADDITIONAL STORM DRAINAGE INFORMATION AND DETAILS.
- 3. REFER TO SHEETS C-4.00 AND C-6.20 FOR ADDITIONAL UTILITY INFORMATION AND DETAILS.
- NOTES

Š **D**NG SNC Z ō Õ 4

HIG

CITY OF HIGH POINT 211 S HAMILTON STREET HIGH POINT, NC 27260

CLIENT:

REVISIONS:

,	
DRAWN:	B\
DATE:	5/20

336) 883-8515	
RAWN:	BW

WN:	BWC
E:	5/20/19

18-330 JOB. NO: SHEET TITLE:

SANITARY & **STORM SEWER** PROFILES

SCALE: H: 1" = 40', V: 1" = 4' SHEET NO .:

- WILL NOT ERODE.
- GENERAL NOTES:

NOTE: CONTINUE FENCE COMPLETELY ALONG AREA TO BE PROTECTED. NO FILL

- STEEL/WOOD (2"x2") POST

BLAZE ORANGE SYNTHETIC BARRICADE

MESH (OR APPROVED EQUAL) TO -

BE FASTENED TO PÓSTS

6'-0" O.C. POST TO POST

MATERIALS OR EQUIPMENT TO BE

STORED OUTSIDE FENCE.

KEEP MUD AND SEDIMENT OFF PUBLIC ROADS.

<u>CONDITIONS WHERE PRACTICE APPLIES:</u> WHEREVER TRAFFIC WILL BE LEAVING A CONSTRUCTION SITE AND MOVING DIRECTLY ONTO A

PUBLIC ROAD OR OTHER PAVED OFF-SITE AREAS. CONSTRUCTION

PLANS SHOULD LIMIT ACCESS TO PROPERLY CONSTRUCTED

* THE TEMPORARY STONE DOUGHNUT SHALL BE REMOVED AND THE AREA STABILIZED WHEN THE REMAINING DRAINAGE AREA HAS BEEN PROPERLY STABILIZED.

* SEDIMENT SHALL BE REMOVED AND SEDIMENT STORAGE AREA RESTORED TO ITS ORIGINAL DIMENSIONS WHEN SEDIMENT HAS ACCUMULATED TO 1/2 THE DESIGN DEPTH OF THE SEDIMENT STORAGE AREA. REMOVED SEDIMENT SHALL SHALL BE DEPOSITED IN A SUITABLE AREA AND IN SUCH A MANNER THAT IT

SECTION A-A

6" THICK 6" THICK FLON ANCHOR FILTER FABRIC SKIRT IN 6" OF STONE <u> | • ' , • · ' • , • · ' • , • · '</u>

CLASS A RIP RAP-#57 WASHED STONE #57 WASHED STONE

SILT FENCE 2 SCALE: NTS

4' STEEL POST 8' O.C.

FILTER FABRIC

EXTENSION OF

(6" MAX. SPACING) AND

WITH 12 GAUGE WIRE MESH

TOP OF CURE GUTTERLINE

NOTES: SEDIMENT CONTROL BAG TO BE PLACED IN DRAINAGE STRUCTURES AS SHOWN ON THE PLANS. BAGS SHALL RECEIVE WEEKLY MAINTENANCE, OR AS REQUIRED AND REPLACED AS NECESSARY.

SILT FENCE OUTLET

HARDWARE CLOTH & **GRAVEL INLET PROTECTION**

SEDIMENT BAG INLET PROTECTION

NCBEES CERT. NO.: C-1347

PRELIMINARY DRAWING NOT FOR CONSTRUCTION

PROJECT:

NC POINT

CLIENT:

CITY OF HIGH POINT 211 S HAMILTON STREET HIGH POINT, NC 27260 (336) 883-8515

© STIMMEL ASSOCIATES, P.A.

- 1. PREPARE SOIL BEFORE INSTALLING ROLLED EROSION CONTROL PRODUCTS (RECPS), INCLUDING ANY NECESSARY APPLICATION OF LIME, FERTILIZER, AND SEED.
- 2. BEGIN AT THE TOP OF THE CHANNEL BY ANCHORING THE RECPS IN A 6"(15CM) DEEP X 6"(15CM) WIDE TRENCH WITH APPROXIMATELY 12"(30CM) OF RECPS EXTENDED BEYOND THE UP-SLOPÉ PORTION OF THE TRENCH. USE MATTING AT THE CHANNEL/CULVERT OUTLET AS SUPPLEMENTAL SCOUR PROTECTION AS NEEDED. ANCHOR THE RECPS WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12"(30CM) APART IN THE BOTTOM OF THE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING. APPLY SEED TO THE COMPACTED SOIL AND FOLD THE REMAINING 12"(30CM) PORTION OF RECPS BACK OVER THE SEED AND COMPACTED SOIL. SECURE RECPS OVER COMPACTED SOIL WITH A ROW OF STAPLES/STAKES SPACED APPROXIMATELY 12" APART ACROSS THE WIDTH OF THE RECPS.
- 3. ROLL CENTER RECPS IN DIRECTION OF WATER FLOW IN BOTTOM OF CHANNEL. RECPS WILL UNROLL WITH APPROPRIATE SIDE AGAINST THE SOIL SURFACE. ALL RECPS MUST BE SECURELY FASTENED TO SOIL SURFACE BY PLACING STAPLES/STAKES IN APPROPRIATE LOCATIONS AS SHOWN IN THE STAPLE PATTERN GUIDE.
- 4. PLACE CONSECUTIVE RECPS END-OVER-END (SHINGLE STYLE) WITH A 4"-6" OVERLAP. USE A DOUBLE ROW OF STAPLES STAGGERED 4" APART AND 4" ON CENTER TO SECURE RECPS.
- 5. FULL LENGTH EDGE OF RECPS AT TOP OF SIDE SLOPES MUST BE ANCHORED WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12"(30CM) APART IN A 6"(15CM) DEEP X 6"(15CM) WIDE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING.
- 6. ADJACENT RECPS MUST BE OVERLAPPED APPROXIMATELY 2"-5" (5-12.5CM) (DEPENDING ON RECPS TYPE) AND STAPLED.
- 7. IN HIGH FLOW CHANNEL APPLICATIONS A STAPLE CHECK SLOT IS RECOMMENDED AT 30 TO 40 FOOT (9 -12M) INTERVALS. USE A DOUBLE ROW OF STAPLÉS STAGGERED 4"(10CM) APART AND 4"(10CM) ON CENTER OVER ENTIRE WIDTH OF THE CHANNEL.
- 8. THE TERMINAL END OF THE RECPS MUST BE ANCHORED WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" (30CM) APART IN A 6"(15CM) DEEP X 6"(15CM) WIDE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING.

SEALS:

NCBEES CERT. NO.: C-1347

PRELIMINARY DRAWING NOT FOR CONSTRUCTION

PROJECT:

SNC POINT HIGH

CLIENT:

PART III SELF-INSPECTION, RECORDKEEPING AND REPORTING

SECTION A: SEL	F-INSPECTION			
Self-inspections below. When a personnel to be which it is safe t greater than 1.0 performed upor were delayed sh	are required duri dverse weather of in jeopardy, the i to perform the ins inch occurs outsi the commencem nall be noted in th	ng normal business hours in accordance with the table r site conditions would cause the safety of the inspection nspection may be delayed until the next business day on pection. In addition, when a storm event of equal to or de of normal business hours, the self-inspection shall be nent of the next business day. Any time when inspections e Inspection Record.	SECTION B: RECORDREEPING 1. E&SC Plan Documentation The approved E&SC plan as well as any a approved E&SC plan must be kept up-to- The following items pertaining to the E&S described:	pproved deviation shall be kept on the site. The date throughout the coverage under this permit SC plan shall be documented in the manner
			Item to Document	Documentation Requirements
Inspect	Frequency (during normal business hours)	Inspection records must include:	(a) Each E&SC Measure has been installed and does not significantly deviate from the	Initial and date each E&SC Measure on a copy of the approved E&SC Plan or complete, date
(1) Rain gauge maintained in good working order	Daily	Daily rainfall amounts. If no daily rain gauge observations are made during weekend or holiday periods, and no individual-day rainfall information is available, record the cumulative rain measurement for those un- attended days (and this will determine if a site inspection is needed). Days on which no rainfall occurred shall be recorded as "zero." The permittee may use another rain-monitoring device	shown on the approved E&SC Plan.	and sign an inspection report that lists each E&SC Measure shown on the approved E&SC Plan. This documentation is required upon the initial installation of the E&SC Measures or if the E&SC Measures are modified after initial installation.
(2) E&SC Measures	At least once per 7 calendar days and within 24 hours of a rain	 approved by the Division. 1. Identification of the measures inspected, 2. Date and time of the inspection, 3. Name of the person performing the inspection, 4. Indication of whether the measures were operating 	(b) A phase of grading has been completed.	Initial and date a copy of the approved E&SC Plan or complete, date and sign an inspection report to indicate completion of the construction phase.
(3) Stormwater	event ≥ 1.0 inch in 24 hours At least once per	 properly, 5. Description of maintenance needs for the measure, 6. Description, evidence, and date of corrective actions taken. 1. Identification of the discharge outfalls inspected, 	(c) Ground cover is located and installed in accordance with the approved E&SC Plan.	Initial and date a copy of the approved E&SC Plan or complete, date and sign an inspection report to indicate compliance with approved ground cover specifications.
discharge outfalls (SDOs)	7 calendar days and within 24 hours of a rain event \geq 1.0 inch in 24 hours	 Date and time of the inspection, Name of the person performing the inspection, Evidence of indicators of stormwater pollution such as oil sheen, floating or suspended solids or discoloration, Indication of visible sediment leaving the site, 	(d) The maintenance and repair requirements for all E&SC Measures have been performed.	Complete, date and sign an inspection report.
(4) Perimeter of site	At least once per 7 calendar days and within 24 hours of a rain	 6. Description, evidence, and date of corrective actions taken. If visible sedimentation is found outside site limits, then a record of the following shall be made: 1. Actions taken to clean up or stabilize the sediment that has left the site limits, 	(e) Corrective actions have been taken to E&SC Measures.	Initial and date a copy of the approved E&SC Plan or complete, date and sign an inspection report to indicate the completion of the corrective action.
(5) Streams or wetlands onsite or offsite (where accessible)	event \geq 1.0 inch in 24 hours At least once per 7 calendar days and within 24 hours of a rain event \geq 1.0 inch in 24 hours	 2. Description, evidence, and date of corrective actions taken, and 3. An explanation as to the actions taken to control future releases. If the stream or wetland has increased visible sedimentation or a stream has visible increased turbidity from the construction activity, then a record of the following shall be made: Description, evidence and date of corrective actions taken, and Records of the required reports to the appropriate Division 	2. Additional Documentation In addition to the E&SC Plan documents a site and available for agency inspectors at all Division provides a site-specific exemption	above, the following items shall be kept on the times during normal business hours, unless the on based on unique site conditions that make thi
(6) Ground stabilization measures	After each phase of grading	 1. The phase of grading (installation of perimeter E&SC measures, clearing and grubbing, installation of storm drainage facilities, completion of all land-disturbing activity, construction or redevelopment, permanent ground cover). 2. Documentation that the required ground stabilization measures have been provided within the required timeframe or an assurance that they will be provided as soon as possible. 	 requirement not practical: (a) This general permit as well as the ce (b) Records of inspections made during the required observations on the Insa similar inspection form that include electronically-available records in lie shown to provide equal access and upper section form that include the shown to provide equal access and upper section. 	rtificate of coverage, after it is received. the previous 30 days. The permittee shall record spection Record Form provided by the Division o les all the required elements. Use of u of the required paper copies will be allowed if itility as the hard-copy records.

NOTE: The rain inspection resets the required 7 calendar day inspection requirement.

NCG01 SELF-INSPECTION, RECORDKEEPING AND REPORTING

PART III SELF-INSPECTION, RECORDKEEPING AND REPORTING

- (c) All data used to complete the Notice of Intent and older inspection records shall be maintained for a period of three years after project completion and made available upon request. [40 CFR 122.41]

SECTION C: REPORTING

- 1. Occurrences that must be reported Permittees shall report the following occurrences:
- (b) Oil spills if:
- - They are within 100 feet of surface waters (regardless of volume).

- environment.

2. Reporting Timeframes and Other Requirements

After a permittee becomes aware of an occurrence that must be reported, he shall contact the appropriate Division regional office within the timeframes and in accordance with the other requirements listed below. Occurrences outside normal business hours may also be reported to the Division's Emergency Response personnel at (800) 662-7956, (800) 858-0368 or (919) 733-3300.

Occurrence		
(a) Visible sediment		
deposition in a		
stream or wetland		
(b) Oil spills and		
release of		
hazardous		
substances per Item		
1(b)-(c) above		
(c) Anticipated		
bypasses [40 CFR		
122.41(m)(3)]		
(d) Unanticipated		
bypasses [40 CFR		
122.41(m)(3)]		
(e) Noncompliance		
with the conditions		
of this permit that		
may endanger		
health or the		
environment[40		
-		

CFR 122.41(I)(7)]

PART III

SELF-INSPECTION, RECORDKEEPING AND REPORTING

(a) Visible sediment deposition in a stream or wetland.

• They are 25 gallons or more,

- They are less than 25 gallons but cannot be cleaned up within 24 hours,
- They cause sheen on surface waters (regardless of volume), or

(a) Releases of hazardous substances in excess of reportable quantities under Section 311 of the Clean Water Act (Ref: 40 CFR 110.3 and 40 CFR 117.3) or Section 102 of CERCLA (Ref: 40 CFR 302.4) or G.S. 143-215.85.

(b) Anticipated bypasses and unanticipated bypasses.

(c) Noncompliance with the conditions of this permit that may endanger health or the

Reporting Timeframes (After Discovery) and Other Requirements

- Within 24 hours, an oral or electronic notification.
- Within 7 calendar days, a report that contains a description of the sediment and actions taken to address the cause of the deposition. Division staff may waive the requirement for a written report on a case-by-case basis.
- If the stream is named on the NC 303(d) list as impaired for sedimentrelated causes, the permittee may be required to perform additional monitoring, inspections or apply more stringent practices if staff determine that additional requirements are needed to assure compliance with the federal or state impaired-waters conditions.
- Within 24 hours, an oral or electronic notification. The notification shall include information about the date, time, nature, volume and location of the spill or release.
- A report at least ten days before the date of the bypass, if possible. The report shall include an evaluation of the anticipated quality and effect of the bypass.
- Within 24 hours, an oral or electronic notification.
- Within 7 calendar days, a report that includes an evaluation of the quality and effect of the bypass.
- Within 24 hours, an oral or electronic notification.
- Within 7 calendar days, a report that contains a description of the noncompliance, and its causes; the period of noncompliance, including exact dates and times, and if the noncompliance has not been corrected, the anticipated time noncompliance is expected to continue; and steps taken or planned to reduce, eliminate, and prevent reoccurrence of the noncompliance. [40 CFR 122.41(l)(6).
- Division staff may waive the requirement for a written report on a case-by-case basis.

EFFECTIVE: 04/01/19

NCBEES CERT. NO.: C-1347

PRELIMINARY DRAWING NOT FOR CONSTRUCTION

PROJECT:

NC POINT

CLIENT:

DRAWN:	BWC	
DATE:	5/20/19	
REVISIONS:		
JOB. NO:	18-330	
SHEET TITLE:		
FROSION		
CONTROL		
DETAILS		

GROUND STABILIZATION AND MATERIALS HANDLING PRACTICES FOR COMPLIANCE WI THE NCG01 CONSTRUCTION GENERAL PERMIT

Implementing the details and specifications on this plan sheet will result in the construction activity being considered compliant with the Ground Stabilization and Materials Handling sections of the NCG01 Construction General Permit (Sections E and F, respectively). The permittee shall comply with the Erosion and Sediment Control plan approved by the delegated authority having jurisdiction. All details and specifications shown on this sheet may not apply depending on site conditions and the delegated authority having jurisdiction

SECTION E: GROUND STABILIZATION

Required Ground Stabilization Timeframes				
Site Area Description		Stabilize within this many calendar days after ceasing land disturbance		
(a)	Perimeter dikes, swales, ditches, and perimeter slopes	7	None	
(b)	High Quality Water (HQW) Zones	7	None	
(c)	Slopes steeper than 3:1	7	If slopes are 10' or less in length and are not steeper than 2:1, 14 days are allowed	
(d)	Slopes 3:1 to 4:1	14	 -7 days for slopes greater than 50' in length and with slopes steeper than 4:1 -7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed 	
(e)	Areas with slopes flatter than 4:1	14	 -7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zon -10 days for Falls Lake Watershed unless there is zero slope 	

Note: After the permanent cessation of construction activities, any areas with temporary ground stabilization shall be converted to permanent ground stabilization as soon as practicable but in no case longer than 90 calendar days after the last land disturbing activity. Temporary ground stabilization shall be maintained in a manner to render the surface stable against accelerated erosion until permanent ground stabilization is achieved

GROUND STABILIZATION SPECIFICATION

Stabilize the ground sufficiently so that rain will not dislodge the soil. Use one of the techniques in the table below:

Temporary Stabilization	Permanent Stabilization
 Temporary grass seed covered with straw or other mulches and tackifiers Hydroseeding Rolled erosion control products with or without temporary grass sood 	 Permanent grass seed covered with straw or other mulches and tackifiers Geotextile fabrics such as permanent soil reinforcement matting Hydrospeding
 Appropriately applied straw or other mulch Plastic sheeting 	 Hydroseeding Shrubs or other permanent plantings covered with mulch Uniform and evenly distributed ground cover sufficient to restrain erosion Structural methods such as concrete, asphalt or

retaining walls

Rolled erosion control products with grass seed

POLYACRYLAMIDES (PAMS) AND FLOCCULANTS

- 1. Select flocculants that are appropriate for the soils being exposed during
- construction, selecting from the NC DWR List of Approved PAMS/Flocculants.
- 2. Apply flocculants at or before the inlets to Erosion and Sediment Control Measures
- 3. Apply flocculants at the concentrations specified in the NC DWR List of Approved PAMS/Flocculants and in accordance with the manufacturer's instructions.
- 4. Provide ponding area for containment of treated Stormwater before discharging offsite.
- Store flocculants in leak-proof containers that are kept under storm-resistant cove 5. or surrounded by secondary containment structures.

NCG01 GROUND

EQUI	PMENT AND VEHICLE MAINTENANCE		
1.	Maintain vehicles and equipment to prevent discharge of fluids.		
2.	Provide drip pans under any stored equipment.	l R	
3.	Identify leaks and repair as soon as feasible, or remove leaking equipment from the project.		
4.	Collect all spent fluids, store in separate containers and properly dispose as hazardous waste (recycle when possible).		
5.	Remove leaking vehicles and construction equipment from service until the problem has been corrected.		CLEARLY M NUTING DEV
6.	Bring used fuels, lubricants, coolants, hydraulic fluids and other petroleum products to a recycling or disposal center that handles these materials.		PLAN.
			BE
	Never bury or burn waste. Place litter and debris in approved waste containers		:
	Drovide a sufficient number and size of waste containers (o g dumpstor, trash		
2.	receptacle) on site to contain construction and domestic wastes.	$\frac{\text{CONO}}{1.}$	Do not
3.	waters unless no other alternatives are reasonably available.	2.	Dispos and sta
4.	Locate waste containers on areas that do not receive substantial amounts of runoff from upland areas and does not drain directly to a storm drain, stream or wetland.	3.	Manag additio
5.	Cover waste containers at the end of each workday and before storm events or provide secondary containment. Repair or replace damaged waste containers.	Δ	lot per
6.	Anchor all lightweight items in waste containers during times of high winds.		alterna
7.	Empty waste containers as needed to prevent overflow. Clean up immediately if containers overflow.		review
8	Dispose waste off-site at an approved disposal facility	5	Donot
о. 9	On business days, clean up and disnose of waste in designated waste containers		section
5.	on business days, clean up and dispose of waste in designated waste containers.		dischar
PAIN	AND OTHER LIQUID WASTE	6	Locate
	Do not dump paint and other liquid waste into storm drains, streams or wetlands.		can be
2.	Locate paint washouts at least 50 feet away from storm drain inlets and surface		install
	waters unless no other alternatives are reasonably available.		spills o
3.	Contain liquid wastes in a controlled area.	7.	Locate
4.	Containment must be labeled, sized and placed appropriately for the needs of site.		entran
5.	Prevent the discharge of soaps, solvents, detergents and other liquid wastes from		approv
	construction sites.	8.	Install :
			limits.
	Install portable toilets on level ground, at least 50 feat away from storm drains	9.	Remov
1.	streams or wetlands unless there is no alternative reasonably available. If 50 foot		overflo
	offset is not attainable, provide relocation of portable toilet behind silt fence or place		compo produc
2.	Provide staking or anchoring of portable toilets during periods of high winds or in high	10.	At the in an a
2	Nonitor portable toilets for leaking and properly dispass of any leaked material		caused
э.	Utilize a licensed sanitary waste hauler to remove leaking portable toilets and replace with properly operating unit		
		HERB	ICIDES,
EART	HEN STOCKPILE MANAGEMENT	1.	restrict
1.	Show stockpile locations on plans. Locate earthen-material stockpile areas at least 50 feet away from storm drain inlets, sediment basins, perimeter sediment controls	2.	Store h
	and surface waters unless it can be shown no other alternatives are reasonably available.		accider
2.	Protect stockpile with silt fence installed along toe of slope with a minimum offset of five feet from the toe of stockpile.	3.	possibl
3.	Provide stable stone access point when feasible		or surfa
4	Stabilize stockpile within the timeframes provided on this sheet and in accordance	4.	Do not
	with the approved plan and any additional requirements. Soil stabilization is defined		
	as vegetative, physical or chemical coverage techniques that will restrain accelerated	H A7A	
	erosion on disturbed soils for temporary or permanent control needs.		Croate
		2.	ridce Na
		J.	י not סע

e concrete or cement slurry from the site.

ecycle settled, hardened concrete residue in accordance with local waste regulations and at an approved facility.

ut from mortar mixers in accordance with the above item and in he mixer and associated materials on impervious barrier and within t fence.

ry concrete washouts per local requirements, where applicable. If an od or product is to be used, contact your approval authority for roval. If local standard details are not available, use one of the two rary concrete washouts provided on this detail.

crete washouts for dewatering or storing defective curb or sidewalk nwater accumulated within the washout may not be pumped into or ne storm drain system or receiving surface waters. Liquid waste must and removed from project.

s at least 50 feet from storm drain inlets and surface waters unless it hat no other alternatives are reasonably available. At a minimum, on of storm drain inlet(s) closest to the washout which could receive

s in an easily accessible area, on level ground and install a stone front of the washout. Additional controls may be required by the ority.

one sign directing concrete trucks to the washout within the project nage on the washout itself to identify this location.

s from the washout when at approximately 75% capacity to limit Replace the tarp, sand bags or other temporary structural nen no longer functional. When utilizing alternative or proprietary manufacturer's instructions.

on of the concrete work, remove remaining leavings and dispose of disposal facility. Fill pit, if applicable, and stabilize any disturbance val of washout.

ES AND RODENTICIDES

herbicides, pesticides and rodenticides in accordance with label

pesticides and rodenticides in their original containers with the s directions for use, ingredients and first aid steps in case of ning.

rbicides, pesticides and rodenticides in areas where flooding is re they may spill or leak into wells, stormwater drains, ground water . If a spill occurs, clean area immediately.

these materials onsite.

KIC WASTE

ed hazardous waste collection areas on-site.

waste containers under cover or in secondary containment.

ardous chemicals, drums or bagged materials directly on the ground.

EFFECTIVE: 04/01/19

NCBEES CERT. NO.: C-1347

PRELIMINARY DRAWING NOT FOR CONSTRUCTION

PROJECT:

SNC POINT

CLIENT:

DRAWN:	BWC
DATE:	5/20/19
REVISIONS:	
JOB. NO:	18-330
SHEET TITLE:	
EROSION	
CONTROL	_

CATCH BASIN

SCALE: NTS

CATCH BASIN HOOD & FRAME

SCALE: NTS

、´З `

CATCH BASIN GRATE

5

2

DENSEL' PLACED

BKH

SCALE: NTS

STORM SEWER TRENCH & BEDDING

STORM MANHOLE

STORM MANHOLE RING & COVER

CLIENT:

Section 272

Engineered Surface Drainage Products

GENERA

NCBEES CERT. NO.: C-1347

PRELIMINARY DRAWING NOT FOR CONSTRUCTION

PROJECT:

NC Z \overline{O} Δ Т <u>U</u> Т

CLIENT:

CITY OF HIGH POINT 211 S HAMILTON STREET HIGH POINT, NC 27260 (336) 883-8515

© STIMMEL ASSOCIATES, P.A.

SEWER PIPE **BEDDING REQUIREMENTS** 7 SCALE: NTS

SCALE: NTS

THRUST BLOCKING DETAIL

NC POINT HIGH

CLIENT:

CITY OF HIGH POINT 211 S HAMILTON STREET HIGH POINT, NC 27260 (336) 883-8515

DRAWN: DATE: **REVISIONS**:

BWC 5/20/19

18-330

JOB. NO: SHEET TITLE: UTILITY

DETAILS

SCALE: SHEET NO .:

C-6.20 © STIMMEL ASSOCIATES, P.A.

SCALE: NTS

PROJECT:

SO Δ HIGH

CLIENT:

TYPICAL SINGLE BRICK BORDER PAVING PATTERN

PROJECT:

NC POINT HIGH

CLIENT:

© STIMMEL ASSOCIATES, P.A.

3-330\Drawings\CD\18-330 L-1.00 LANDSCAPE PLAN.dwg : L-1.00 06/24/19

Content of the second state of the second stat

LANDSCAPE WORK SPECIFICATIONS:

PART 1 - GENERAL

DESCRIPTION OF WORK

Extent of landscape work includes furnishing all materials, equipment and labor necessary for preparation of final subgrades in planting areas; distribution/ application of topsoil; soil treatment; planting of trees and shrubs; protection/ maintenance/guarantee/replacement of plants; related items required to complete work indicated on drawings and specifications. (See Landscape Plan.)

GUARANTEE:

Guarantee trees/shrubs/lawn/grass for period of one year after date of acceptance, against defects including death and unsatisfactory growth, except for defects resulting from neglect by Owner, abuse/damage by others, or unusual phenomena/incidents which are beyond landscape installer's control.

Remove/replace trees, shrubs, grass or other plants found to be dead or in unhealthy condition during warranty period. Make replacements during growth season following end of warranty period. Replace trees/shrubs which are in doubtful condition at end of warranty period, unless, in opinion of Landscape Architect, it is advisable to extend warranty period for a full-growing season.

Another inspection will be conducted at end of extended warranty period, if any, to determine acceptance/rejection. Only one replacement will be required at end of guarantee period, except for losses/replacements due to failure to comply with specified requirements.

INDUSTRY STANDARDS:

Some products and execution are specified in this Section by reference to published specifications or standards of the following (with respective abbreviations used). Reference is to the latest edition of the standard referenced. The American Society for Testing and Materials (ASTM)

Association of Official Agricultural Chemists (AOAC)

American Association of Nurserymen (AAN) U.S. Department of Agriculture (USDA)

SUBMITTALS:

Substitutions shall not be considered unless it can be reasonably demonstrated that material specified is or shall be unavailable within 500 miles of the site of the work at the time of installation. Landscape Architect shall authorize the nearest equivalent obtainable size/variety of plant having some essential characteristics with equitable adjustment of contract price. Unit price of substituted item shall not exceed bid item being replaced. All submittal requests are to be made in writing.

Certificates: All material whose transportation requires inspection and/or certification by any governmental agency shall be accompanied by copies of certification or inspection which shall be given to a selected representative at the site at the time of delivery.

Soil PH Testing: Landscape contractor to submit a soil sample to test the current PH Level, once beds are defined and prior to any planting. The PH Level must be (5.8-6.2) and approved by the Landscape Architect prior to any plant installation

QUALITY ASSURANCE:

General: Ship landscape materials covered and with certificates of inspection required by governing authorities. Comply with regulations applicable to landscape materials. All plant material must be "nursery grown". All plant material collected from naturalized areas will be rejected.

Soil Ph: Landscape Contractor to submit a soil sample, once beds are amended and prior to planting. The Ph must be correct and checked by Landscape Architect prior to any planting.

Topsoil: Provide topsoil of a type that is in compliance with Part 2 - Products of this section.

Plant List: List of plants as shown on drawings (Sheets L-1.0).

Quantities: Quantities necessary to complete plantings as shown/located on drawings shall be furnished. Quantities shown in list are for convenience of contractors and believed to be substantially correct, but accuracy of quantities in list is not guaranteed.

Trees and Shrubs: Provide trees and shrubs grown in a recognized nursery in accordance with good horticultural practice. Provide healthy, vigorous stock free of disease, insects, eggs, larvae, and defects such as knots, sun-scald, injuries, abrasions, or disfigurement. All shade trees to be 'A' grade trees (see detail below).

Sizes: Provide trees and shrubs of sizes shown or specified in Plant List, which are minimum acceptable sizes and shall be measured before pruning with branches in normal position. Any necessary pruning shall be done at time of planting. Trees and shrubs of larger size may be used if acceptable to Landscape Architect, and if sizes of roots or balls are increased proportionately.

Tagging Trees: Landscape Architect reserves the right to tag specimen trees (See General Notes) at place of growth for compliance with requirements for size and quality assurance. Landscape Contractor recommended to use the following nurseries for the supply of trees:

-Shady Grove	(803-534-5683)
-Bold Springs	(770-267-9196)
-Green Thumb	(910-428-4587)
-Worthington Farms	(252-756-3827)

-Select Trees (706-769-9879) -Lone Oak (706-637-6240) -Gilmore Plant & Bulb Co. (336-685-4451)

Inspection: Landscape Architect reserves the right to inspect trees and shrubs either at place of growth or at site, for compliance with requirements for name, variety, size and quality

DELIVERY, STORAGE AND HANDLING:

Packaged Materials: Deliver packaged materials in containers showing weight, analysis and name of manufacturer. Protect materials from deterioration during delivery, and while stored at site.

Trees, Shrubs & Transplanted Trees: Provide freshly dug trees and shrubs. Do not prune prior to delivery. Do not bend or bind-tie trees or shrubs in such manner as to damage bark, break branches or destroy natural shape. Provide protective covering during delivery. All trees, shrubs & groundcovers much be delivered in a completely tarped and covered vehicle or the entire load will be refused. Immediately after unloading, trees to be set upright never placed lying down. Always lift and move trees by strapping on root ball or by using chain cradle on the root ball for larger root balls.

JOB CONDITIONS:

Utilities: Determine location of underground utilities and perform work in a manner which will avoid possible damage. Hand excavate, as required. Maintain grade stakes set by others until removal is mutually agreed upon by parties concerned.

Coordination with Other Work: Plant new trees and shrubs after final grades are established and prior to planting of lawns, unless otherwise acceptable to Landscape Architect. If planting of trees and shrubs occurs after lawn work, protect lawn areas and promptly repair damage to lawns resulting from planting operations.

PART 2 - PRODUCTS

Topsoil: Additional topsoil to be furnished at no cost to Owner. Topsoil to be natural, fertile, friable soil, possessing characteristics of representative productive soils in vicinity; obtained from naturally well-drained areas; not excessively acid/ alkaline nor contain toxic substances harmful to plant growth; without admixture of subsoil and cleaned and reasonably free from clay/lumps/stone/ stumps/roots or similar substances 2" or more in diameter/debris/objects which might hinder planting operations.

Lime: Ground limestone containing not less than 85% total carbonates to such fineness that 50% will pass through a 100-mesh sieve and 90% will pass through a 20-mesh sieve. Use as necessary for specific plants.

Commercial Fertilizer: Organic fertilizer Stay Green Nursery Special 12-6-6 or approved equal; delivered dry/free-flowing in original unopened containers, each bearing manufacturer's guaranteed analysis, shall conform to applicable State Fertilizer laws. Any fertilizer which becomes caked/damaged, making it unsuitable for use, will not be

Pre-emergence Herbicide: Landscape Contractor to apply pre-emergence Herbicides as per manufacturer's specifications in all plant beds prior to final mulch application.

Soil **M**ix: All plant beds shall be composed of the following: 1 part Existing Soil 1 part Topsoil

1 part Pine Bark Soil Conditioner

Soil Conditioner: Soil Conditioner shall be small pine bark particles of 3/8" or less, provided in prepackaged bags or approved bulk delivery.

Mulch

displacement: bed mulched instead of pit mulched.

Materials for Staking Trees: Contractor shall place stakes of sound new hardwood, treated softwood or redwood, free

turnbuckles. Provide not less than 1/2" hose, cut to required lengths to protect tree trunks from damage.

PART 3 - EXECUTION

PLANTING:

Layout: Location for plants/outlines of areas to be planted are indicated on plan. Where construction and utilities below ground or overhead are encountered or where changes have been made in construction, necessary adjustments to be approved by Landscape Architect

Soil Preparation: Soil shall be as specified; be in relatively dry state and mixed thoroughly by hand or rotary mixer. Commercial fertilizer at rate of 2#/c.y. shall be added. All planting beds shall be coated with approved pre-emergence weed killer according to manufacturer's specifications. All shrub planting areas to be bed prepared and not just pit prepared/planted unless approved by Landscape Architect. Soil shall be prepared minimum of one week prior to planting day, for proper settling

topsoil. See Landscape Plans for locations. Landscape Contractor responsible for all fine grading of areas to receive seeding.

For pit/trench backfill, mix planting soil prior to backfilling and stockpile at site. For planting beds, mix planting soil thoroughly prior to planting or apply on surface of topsoil. For plant beds against building foundations, soil mix shall be mixed thoroughly prior to placement. Prevent lime from

Ball/Burlapped Plants: After final setting loosen wrappings of balled/burlapped plants and roll wrappings back from top of ball leaving ball unbroken. Cut off excessive amounts of burlap, remove sufficient quantity to eliminate creation of voids upon decomposition.

Container Grown Plants: These may be applied in lieu of balled/burlapped plants if all other specified requirements are met; plants to have grown in container for minimum of six months and maximum of two years and when delivered, have sufficient root growth to hold earth intact when removed from container; plants must not be root bound. Remove container in way to prevent damage to plant/root system.

Tree Pit Sizes: Minimum diameter/depth of planting pits for balled/burlapped, bare roots and container grown plants shall be 24" greater than diameter of ball/spread of roots and trees sit directly on pit bottom to prevent settlement.

Shrubs/Groundcover: All plant beds for shrubs/groundcovers to be prepared for a total depth of 9" and should consist of 1 part existing soil, 1 part topsoil and 1 part soil conditioner (see soil mix). Till existing soil to a minimum depth of 3"; add 3" of topsoil and till thoroughly; add 3" of pine bark soil conditioner and till with other amendments to a total depth of 9". Entire bed to be covered with 3" of clean hardwood mulch.

planting bed to be seeded with an even mixture of Hunter, Padre, and Magellan tall fescues, or approved equal, at a rate of 5-6 lbs./1,000 s.f. so as to produce a thick, firm stand of grass. Fertilize at a rate of 10 lbs./1,000 s.f. with 10-10-10 slow-release fertilizer (use straw or other material to cover seed until stable.) Apply lime according to soil test, or apply 4,000 lbs./acre slow-release pelletized agricultural limestone.

Seeding dates: Aug. 20 through Oct. 25 and Feb. 1 through May.

Setting Trees: All trees to be planted according to Planting Details shown on Landscape Plans. Unless otherwise specified, all trees to be planted in pits, centered, set on unexcavated soil to depths that finished grade level of plant after settlement shall be same as that which plant was grown; plant upright and faced to give best appearance/ relationship to adjacent structures; plant above grade 3/4" for every foot of ball diameter. Place tree root balls at a level where the trunk flare will be 2" above surrounding finished grade. No burlap to be pulled out from under balls; remove platforms, wire and surplus binding from top/sides of balls; cut broken/frayed roots; place/compact prepared soil to avoid injury to roots and fill all voids. Saturate the planting hole with water after backfill is 3/4 complete and allow to soak away; fill hole to finished grade, allowing 4" of mulch; form shallow saucer around each plant.

Pruning New Plant Material: Remove dead/broken branches from all plant material. Prune all trees/ shrubs to a branch node and remove only as much foliage as necessary for neat appearance while retaining natural growth habit of plant variety. Prune away crossing limbs or water sprouts/ shoots from trees always leaving branch collar intact (no additional stub length). Under cut larger limbs to prevent tearing of the bark. Girdling roots of trees should be cut at this time to prevent future problems. Make all cuts with sharp pruning equipment. Topping of trees and wound painting are NOT permitted. Remove trimmings from the site.

Guying Trees: All canopy trees 2" caliper or greater shall be staked and guyed. Landscape Contractor is responsible to remove all stakes and guys at the end of the one year warranty period. See Planting/Staking Details.

displacement of mulch by thoroughly wetting down. Mulch the area over tree rootballs to a depth no deeper than 1.5-2". Keep all mulch away from the trunk flare. If plant has existing mulch, remove old mulch before applying new mulch.

Excess Excavated Soil: To be disposed of by Contractor at no additional expense to Owner.

MAINTENANCE:

Begin immediately after planting. Maintain trees/shrubs/other plants until final acceptance. Maintain trees/shrubs/other plants by pruning, cultivating, weeding as required for healthy growth. Restore planting saucers; tighten/repair stake and guy supports and reset trees/shrubs to proper grades/vertical position as required. Restore/replace damaged wrappings. Spray as required to keep trees/shrubs free of insects/disease.

CLEANUP AND PROTECTION:

INSPECTION:

maintenance, Landscape Architect will, upon request, make inspection to determine acceptability. Landscape work may be inspected for acceptance in parts agreeable to Landscape Architect, provided work offered for inspection is complete including maintenance. Where inspected landscape work does not comply with requirements, replace rejected work, continue specified maintenance until reinspected by Landscape Architect and found to be acceptable. Remove rejected plants/materials promptly from project site.

- Contractor shall supply/place clean hardwood mulch 3" depth moistened at time of application to prevent wind
- Water: Furnished by Owner, suitable for irrigation and free from ingredients harmful to plant life.
- of knot holes/defects. Provide wire ties/guys of 2-strand twisted, pliable, #2-12 gage, galvanized iron wire, zinc-coated

- Landscape Contractor responsible for all shaping and fine grading of bermed areas. General Contractor to provide
- contacting roots of acid-loving plants. Prepare soil mix as specified to minimum depth of 6" below largest shrub root ball.
- Lawn Seeding: All unpaved disturbed areas (or lawn to be reestablished), excluding areas to be sodded, outside

- Mulching: Trees/shrubs shall be mulched immediately after planting with 3" depth of hardwood mulch. Prevent wind
- During landscape work keep pavements clean, work area in orderly condition; protect work/materials from damage due to landscape operations, operations by other contractors/trades/trespassers. Maintain protection during installation/maintenance periods. Treat/repair/replace damaged landscape work as directed.

See "Landscape Construction Sequence" on Landscape Plans. When landscape work is complete, including

SPECIAL CONDITIONS:

- 1. Landscape contractor is responsible for coordinating a "site acceptance inspection" with the owner, General Contractor and Architect prior to start of construction.
- 2. Landscape contractor to submit a soil sample, once beds are amended and prior to planting. The ph must be correct
- and checked by Landscape Architect prior to any planting 3. Landscape contractor is responsible for providing topsoil in traffic islands so there is a crown of 10-12" at the center
- of each island 4. All canopy trees 2" caliper or greater shall be staked and guyed. Landscape contractor is responsible to remove all
- stakes and guys at the end of the one year warranty period. 5. All tree-form and multi-stem trees to have multiple trunks (min 3 each) and be limbed up a min. of 3.0.' All large canopy trees to have the height of their first branches 5-6' above ground. All columnar and single story trees to have the height of their first branches 4-5' above ground.
- 6. Soil mix for all perennial areas to be 6" thick "metro-mix" from Southern Agricultural Insecticide, Boone, NC (1-800-477-8843).

GENERAL LANDSCAPE NOTES:

1. General contractor to use licensed Landscape Contractors with Landscape Architect prior to bidding. Bids using Landscape Contractors not pre-approved will not be considered.

Landscape contractor to: 1. Follow landscape construction sequence.

- 2. Contact General Contractor prior to submitting bid to verify any phasing of planting areas.
- 3. Fine grade all grass and planting areas disturbed during construction. Remove from site all temporary seeding/stabilization, stones, gravel and all extraneous debris including roots and limbs prior to sodding/seeding.
- When fine grading insure that positive drainage is occurring. 4. Till and amend all plant beds as required in specifications. Apply pre-emergence herbicides per manufacturer's specifications in all plant beds prior to any planting. Cover entire bed with a 3" min. Clean mulch immediately after planting. Site mulch to be clean hardwood mulch except for plant beds at the public doors--use mini-pine bark
- 5. Bring to the attention of the Landscape Architect any debris or poor soils remaining in parking lot islands after general construction and prior to planting
- Verify all underground utilities prior to installation of any plant materials. Utilities shown on plan are for reference only and may not be all inclusive. See General Contractor for as-built drawings for all underground utilities. Provide 3' diameter mulch rings for all trees in grass areas.
- 8. Insure that all tree mulch rings are a minimum of 2.0' from the edges of shrub beds and curbs. 9. Neatly edge all plant bed/grass borders with a straight "v"-cut edge.
- 10. Insure all trees of same variety match in shape and size where they are to be installed in groups, rows or as street
- 11. Obtain authorization prior to any changes of plant location due to utilities or other factors. 12. Protect all existing structures (i.e.. Curb and gutter, pavement, etc.) During installation of large trees and other
- 13. Prior to seeding, verify that all trenching and other land disturbing activities within areas to be seeded have been completed.

LANDSCAPE

CONSTRUCTION SEQUENCE:

Landscape Contractor to:

- 1. Visit site after authorization by General Contractor to begin, and accept/reject condition of site prior to any planting. Stake and till entire plant beds and include fertilizer, pre-emergence herbicides and soil mix per specifications.
- Transport all plants to site covered. Any plants damaged during or prior to shipping to the site will not be accepted. Contact Architect for approval/denial of all plant beds and plant stock prior to installati
- Proceed according to planting plan upon approval by Architect of plants and plant bed staking and preparation. 6. Contact Architect, upon completion of work, for final approval of work.
- 7. Make necessary adjustments for approval. Landscape Contractor responsible for contacting the G.C. to set a
- neeting to review the punch items. Maintain all plant material according to specifications/warranty.
- 9. Immediately remove/replace any dead or dying plants during warranty period.

SOIL MIX (SEE SPECS.)

One part existing soil One part topsoil

One part pine bark soil conditioner Planting bed depth to be a minimum of 9"

SOIL PREPARATION:

- Prepare all shrub beds to a total depth of 9." Till existing subsurface soil to a minimum 3" depth.
- Add 3" of topsoil and till with existing soil. 4. Add 3" of pine bark soil conditioner and till thoroughly with other amendments.

STREET STREETSCAPE & PLANTERS

I. STREET STREETSCAPE, PLANTERS & TREE PITS: A.INITIAL TREE PIT PREPARATION BY LANDSCAPE CONTRACTOR:

- (See Specification below.) 2. Contact Chuck Friedrich, RLA with Carolina Stalite Company Phone: (877) 737-6284
- B TREE PIT EXCAVATION
- to be planted. 2. Stockpile excavated soil on adjacent walkway.
- necessarv

Section 02910 PLANTING MEDIA FOR PLANTERS

PART 1 - GENERAL 1.0 SUMMARY

A. Section Includes: 1. Planting Media B. Related Sections

- 1.01 REFERENCES A. ASTM - American Society for Testing and Materials B. USDA - US Department of Agriculture
- 1.02 DEFINITIONS
- 1.03 SYSTEM DESCRIPTION

A. Planting Media premixed containing the three components below:

- 40% Stalite Recycled Fines 30% USGA Root Zone Sand
- 2**0%** compost 10% Pine Bark Fines

PART 2 - PRODUCTS

2 .01	MATERIALS

۹.	Stalite Recycled	expanded slate fines from	1 5
	Sieve Size	% Retained	
	#4	4-8%	
	#8	28-38%	
	#16	46-58%	
	#30	63-75%	
	#50	74-84%	
	#100	82-90%	
	Fine Material	2.79-3.53 % passing #10	0

B. USGA Root Zone Sand

Sieve Size	% Retained on Sieve
2.00 mm	<3%
1-2 mm	10% max
0.5 -1 mm	45% max
.255 mm	35% - 75%
.1525 mm	15% max
.0515 mm	5% max

- C. Approved Component
- composting process must also meet certification requirements screening and curing
- 3. Metals and contaminants must meet or exceed US EPA Standard 40 2.03 Mixes

A. Planting Media Stalite Recycled Fines USGA Root Zone Sand Approved Compost Pine Bark Fines

3.02 PROTECTION OF SOIL MIXES

A. Contamination and Compaction

as required for protection.

1. Landscape Contractor shall excavate existing tree pits to a depth of 2' and backfill with Stalite Planting Media Soil Blend.

1. The Landscape Contractor shall dig out by hand the existing materials to a depth of equal the height of the root ball of the tree

3. Periodically test the soil remaining in the tree pit for it's suitability to plant proposed trees. Excavate and replace this soil if 4. Place the tree in the pit and plant per Typical Tree Planting Detail and backfill with Stalite Planting Media.

5. Stockpile any remaining Stalite Planting Media Soil Backfill for use in unsuitable soil pits and for other phases of this project

ate fines from screening operation

1. Grain Size Distribution (ASTM C136-95A)

max 5% max

1. Compost must be certified and derived from a non-sewage sludge feedstock source. The addition of yard waste to the

2. Finished compost must be screened to minus 1/2", protected, and free from any outside contaminants during and after

1. Do not deliver or place soils in frozen, wet, or muddy conditions. Do not place materials in an excessively moist condition. 2. When stockpiled, protect soils media from absorbing excess water and from erosion at all times. Do not store materials unprotected from large rainfall events. Do not allow excess water to enter site prior to compaction. If water is introduced into the material after stockpiling, allow material to drain or aerate to optimum compaction moisture content. 3. In handling materials, operating tools and equipment, protect the media from compaction by laying down planking or plywood

4. Pressure wash equipment prior to handling media to prevent weed seed contamination.

SEALS:

NCBEES CERT. NO.: C-1347

PRELIMINARY DRAWING NOT FOR CONSTRUCT

PROJECT:

\mathbf{O}

CLIENT:

CITY OF HIGH POINT 211 S HAMILTON STREET HIGH POINT, NC 27260 (336) 883-8515

RAWN:	JMT
DATE:	5/20/19
REVISIONS:	
OB. NO:	18-330
HEET TITLE:	

LANDSCAPE NOTES, SPECS & DETAILS

SHEET NO .:

City of High Point Project Number <u>29-012418</u> ("the Project")

Change Order No. 4

APPENDIX D Payment Bond Performance Bond **CITY OF HIGH POINT**

PAYMENT BOND

CITY OF HIGH POINT PROJECT NUMBER:

PAYMENT BOND

Principal:		
-	Name of Principal Contractor	
Surety:		
	Name of Surety	
Project Number:	County:	
Bond Amount:		

KNOW ALL MEN BY THESE PRESENTS, That we, the Principal and Surety named above, are held and firmly bound unto the City of High Point in the penal sum of the amount stated above for the payment of which sum well and truly be made, we bind ourselves, our heirs, executors, administrators, and successors, jointly and severally, firmly by these presents.

THE CONDITION OF THIS OBLIGATION IS SUCH, that whereas the Principal entered into a certain contract with the City of High Point identified by the Project Number set forth above, and hereto attached:

NOW, THEREFORE, if the Principal promptly makes payment to all persons supplying labor and material in the prosecution of the work provided for in said contract, and any and all duly authorized modifications of said contract that may hereafter be made, notice of which modifications to the Surety being hereby waived, then this obligation to be void; otherwise to remain in full force and effect;

This payment bond is provided pursuant to and governed by Article 3 of Chapter 44A of the North Carolina General Statutes, N.C. Gen. Stat. §§44A-25 et seq., including but not limited to the statutory provisions regarding claims on this payment bond.

IN WITNESS WHEREOF, the Principal and Surety have caused this instrument to be executed under their several seals on the dates indicated below, the name and corporate seal of each corporate party being hereto affixed and these presents duly signed by its undersigned representative, pursuant to authority of its governing body.

SURETY

By

General Agent or Attorney-in-Fact Signature

Seal of Surety

Print or type Signer's Name

Date:

PRINCIPAL

Ву:	
Printed Name:	
Title:	
Date:	

(Corporate Seal)

CITY OF HIGH POINT

PERFORMANCE BOND

CITY OF HIGH POINT PROJECT NUMBER:

PERFORMANCE BOND

Principal:		
	Name of Principal Contractor	
Surety:		
	Name of Surety	
Project Number:	County:	
Bond Amount:		

KNOW ALL MEN BY THESE PRESENTS, That we, the Principal and Surety named above, are held and firmly bound unto the City of High Point in the penal sum of the amount stated above for the payment of which sum well and truly be made, we bind ourselves, our heirs, executors, administrators, and successors, jointly and severally, firmly by these presents.

THE CONDITION OF THIS OBLIGATION IS SUCH, that whereas the Principal entered into a certain contract with the City of High Point identified by the Project Number set forth above, and hereto attached:

NOW, THEREFORE, if the Principal shall well and truly perform and fulfill all of the undertakings, covenants, terms, conditions, and agreement of said contract during the original term of said contract and any extensions thereof that may be granted by the City of High, with our without notice the Surety, and during the life of any guaranty required under the contract, and shall also well and truly perform and fulfill all the undertakings, covenants, terms, conditions, and agreement of any and all duly authorized modifications of said contract that may hereafter be made, notice of which modifications to the Surety being hereby waived, then, this obligations to be void; otherwise to remain in full force and virtue.

This performance bond is provided pursuant to and governed by Article 3 of Chapter 44A of the North Carolina General Statutes, N.C. Gen. Stat. §§44A-25 et seq., including but not limited to the statutory provisions regarding claims on this performance bond.

IN WITNESS WHEREOF, the Principal and Surety have caused this instrument to be executed under their several seals on the dates indicated below, the name and corporate seal of each corporate party being hereto affixed and these presents duly signed by its undersigned representative, pursuant to authority of its governing body.

SURETY

By

General Agent or Attorney-in-Fact Signature

Seal of Surety

Print or type Signer's Name

Date:

PRINCIPAL

By:	
Printed Name:	
Title:	

Date: _____

(Corporate Seal)